

Changes to Modified Prescriptive Path Requirements document – both 2007 and 2010

- Added note to duct leakage requirement that allows for an alternative method of meeting total duct leakage requirements post-construction.
- Updated requirement for central duct leakage, based on EPA program update, which allows a higher maximum leakage allowance if multiple registers are used per floor.

Changes to 2010 version only

- Packaged terminal heat pumps are no longer allowed in Modified Prescriptive Path projects (for projects required to follow ASHRAE 2010 baseline)
- Updated PTAC requirement to match ASHRAE 189.1-2011 requirement.
- Updated code references to newer version (e.g., ASHRAE 90.1-2007 to ASHRAE 90.1-2010)