



## Introduction to the Fundamentals of the Proper Commissioning Process - Supporting a wide range of simple to complex buildings, technologies and projects

### Presented by:

**Khaled A. Yousef**, PE, CEM, CDSM, LEED AP, GBE  
Principal Energy Engineer / Founder  
Pyramid Energy Engineering Services, PLLC (Pyramid EES)  
30 Karner Road #12369, Albany, NY 12212, USA

[Khaled.A.Yousef@PyramidEES.com](mailto:Khaled.A.Yousef@PyramidEES.com)

+1 (518) 221-7382

[www.PyramidEES.com](http://www.PyramidEES.com)

Energy Efficiency & Sustainability | Optimization | Modeling  
Technical & Design Assistance | Master Planning  
Energy Audits | LEED Support | Commissioning  
CHP | Biomass | RH&C | R&D



1

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Notice

These slides were prepared by Pyramid Energy Engineering Services, PLLC (Pyramid EES); many of which were prepared during the course of performing work contracted for and sponsored by the New York State Energy Research and Development Authority (hereafter "NYSERDA"). The opinions expressed in this report do not necessarily reflect those of NYSERDA or the State of New York, and reference to any specific product, service, process, or method does not constitute an implied or expressed recommendation or endorsement of it. Further, NYSERDA and the State of New York make no warranties or representations, expressed or implied, as to the fitness for particular purpose or merchantability of any product, apparatus, or service, or the usefulness, completeness, or accuracy of any processes, methods, or other information contained, described, disclosed, or referred to in this report. NYSERDA and the State of New York make no representation that the use of any product, apparatus, process, method, or other information will not infringe privately owned rights and will assume no liability for any loss, injury, or damage resulting from, or occurring in connection with, the use of information contained, described, disclosed, or referred to in this report.

### Objectivity and Related Affiliations

Pyramid EES provides objective, independent and third party assistance to customers. Pyramid EES has no equipment, manufacturer, or service affiliations that will affect its impartiality and ability to provide objective and independent services.

2

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### ASHRAE disclaimer

ASHRAE is a Registered Provider with The American Institute of Architects Continuing Education Systems. Credit earned on completion of this program will be reported to ASHRAE Records for AIA members. Certificates of Completion for non-AIA members are available on request.

This program is registered with AIA/ASHRAE for continuing professional education. As such, it does not include content that may be deemed or construed to be an approval or endorsement by the AIA and/or ASHRAE of any material of construction or any method or manner of handling, using, distributing, or dealing in any material or product.

Questions related to specific materials, methods, and services will be addressed at the conclusion of this presentation.

## Course Description - **Stage-I** - (1 of 5)

This course presents an overview to the **proper commissioning (Cx) process** starting with what is Cx? It presents the most known six (6) types of Cx (Total Cx, Continuous Cx, Ongoing Cx, Re-Cx, Retro-Cx, & Cx Light or Custom Cx), the 4 proper phases of the Cx process, how to plan for Cx, the Cx team's composition and their Roles and Responsibilities; it then offers an intro to the required checklists, forms and tests to conduct proper Cx, and how to plan for and generate a beneficial Cx report for existing and new buildings and systems targeting high performance.

Topics Covered / Learning Objectives - Stage-I - (2 of 5)

Understand *well-integrated* and *holistic* project development and Cx approaches to support successful HVAC, MEP and building automation systems (EMS/BMS/SCADA) installations covering a wide variety of conventional, progressive and renewable heating and cooling systems and technologies in varying building types and sizes covering residential, commercial, institutional, industrial facilities (& even laboratories & mission critical facilities!).

**Cx** is part of **IDP** (*Integrated Design Process*).

5

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Topics Covered / Learning Objectives - Stage-I - (3 of 5)

Be aware of the numerous Commissioning (Cx) *procedures and requirements* based on major Cx references by the **U.S. DOE** (The Model Cx Plan - Construction Phase Cx Plan), the US DOE funded **BCxA** (Building Commissioning Association), **ACG** (AABC Cx Group), the well-known and widely accepted **ASHRAE** Guideline 0 (The Cx Process), ASHRAE Guideline 1 (The HVAC Cx Process), as well as numerous respected other resources, all coupled and illustrated by the authors own in-depth expertise and experience in the field over the last 3 decades, domestically in the U.S. as well as internationally, supported by real life examples, some were quite painful and expensive.

6

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Topics Covered / Learning Objectives - Stage-I - (4 of 5)

- Make a differentiation between ***existing*** and ***new*** buildings and provide an overview of suggested additional sensors to incorporate during the design and construction phases to support new building Total Cx then Ongoing Cx moving forward using those built-in sensors for both monitoring based Cx & M&V if needed).
- Identify key systems within a facility that are better candidates or higher priorities for commissioning compared to other systems as sorted by their energy use, demand intensities, more critical to facility operation in terms of occupant comfort, productivity, customer revenues, IEQ and safety.

7

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Topics Covered / Learning Objectives - Stage-I - (5 of 5)

- Be aware of a few of the known ***barriers*** impeding implementation of the proper Cx process in numerous projects and know how to avoid them through good customer and project team education.
- Be aware of the proper Cx process from A to Z and see what happens when the proper process was not followed based on multiple real life examples. Some lessons were real painful and expensive! ***Over 20 lessons learned categories are presented*** (but will be elaborated on further during future Stage-II of this course as such optional and in-depth detail cannot be covered in the short Stage-I course).

8

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Topics Covered / Learning Objectives - Completion of the last Introductory **Stage-I**, then move to **Stage-II**. - (1 of 5)

Due to the 1- to 2- hr time restriction in the **Introductory Cx Stage-I Course**, the in-depth Cx [1] **PFCs** (Prefunctional Checklists) and [2] **FPTs** (Functional Performance Tests) that are technology specific and cover several known HVAC/MEP systems will be presented separately, along with other relevant [3] **Cx procedure details** and [4] **Lessons Learned details** (caused by lack of Cx in several example projects); All will be made available in the full day **Stage-II** Cx course (in the future presenting a full Cx hands-on Workshop - where [5] a **Site Visit** of commissioned systems may also be offered).

9

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Topics Covered / Learning Objectives - Stage-II - (2 of 5)

- During Stage-II of this course, it elaborates and emphasizes the importance of Cx and illustrates the devastating impacts of lack of Cx by sharing details of numerous **lessons learned** from biomass heating system commercial installations pertaining to several High-Efficiency and Low-Emission Biomass Heating projects.
- The course covers varying sizes and a wide range of installations and layouts.

10

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Topics Covered / Learning Objectives - Stage-II - (3 of 5)

- Presents how following the core 4-Phase Cx process ([1] Cx During Pre-Design Phase, [2] Cx During Design Phase, [3] Cx During Construction, and [4] Cx During Occupancy & Operations) may have prevented many of the above problems from occurring; all coupled by valuable and in-depth Cx PFC and FPT technology specific examples and it presents other Cx procedures and details.

### Topics Covered / Learning Objectives - Stage-II - (4 of 5)

- Topics presented include, but are not limited to, system sizing, controls, systems integration between existing oil/propane boiler plants and the new biomass heating boiler plants, Commissioning (Cx), Testing, Adjusting and Balancing (TAB), Thermal Energy Storage (TES), hydronics, boiler venting, mechanical room layouts, differences between stick-built vs. containerized boiler plant options, project management (PM), construction management (CM), and project roles and responsibilities (R&R) from A to Z.

### Topics Covered / Learning Objectives - Stage-II - (5 of 5)

- Promotes well-integrated and holistic project development approaches to support successful biomass installations and support the entire biomass heating industry.
- Also shares a list of valuable conclusions, recommendations, suggested next steps, and valuable take home messages.
- Finally, audience will acquire other benefits and skills that will support them in their daily job besides biomass heating.

## Important Cx Related Definitions, Sources & Resources

In general, Commissioning is a systematic process of inspecting and testing building systems to ensure that they are installed properly and operate in accordance with the design intent.

Listed below are General Definitions and elaborations in relation to Commissioning & TAB.

These are based on industry-accepted standards and cover **all phases** of the project. Quotations below come from several valuable ASHRAE (and other) References published over the last 20+ years:

**“Total Building Commissioning Process (TBCxP):**

Very  
Important  
Slide

- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Cx Process** as “A quality-focused **process** for enhancing the delivery of a project. The process focuses upon verifying and documenting that the facility and all of its systems and assemblies are planned, designed, installed, tested, operated, and maintained to meet the Owner’s Project Requirements”.
- “The Cx **Process begins** at project inception during the Predesign Phase and continues for the life of the facility through the Occupancy/Operations Phase. During the Predesign Phase, the OPR are determined and documented by the Cx Team, which includes the Owner, Cx Authority (CxA), design professionals, operation and maintenance personnel, occupants, and users. Throughout each phase of the project, deliverables (drawings, specifications, submittals, construction, training, documentation, etc.) are verified against the OPR”.



### **Total Building Commissioning Process (TBCxP):**

Per ASHRAE, The Commissioning Process, also published by NIBS (National Institute of Building Sciences) as Guideline 0, fully supports the **Total** Building Commissioning Process.

- Q. What does **Total** Mean?
- **Total = Holistic = Thorough = Complete = Extensive = Multi-Phase = Full 4-Phase Cx Process = Spans from pre-design all the way into occupancy = The Cadillac = Get it done right all the way from the project beginning to its end, be thorough and do not cut corners.**



**A Comprehensive Total Building Commissioning Process (TBCxP) takes place in Four (4) Phases of the project:**

Per the ASHRAE **Cx Guidelines**, Total Commissioning can take place in **4 Phases**:

1. Cx During Pre-Design Phase,
2. Cx During Design Phase,
- 3. Cx During Construction**, and
4. Cx During Occupancy & Operations.

**ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Cx Process** as “A quality-focused process for enhancing the delivery of a project. The process focuses upon verifying and documenting that the facility and all of its systems and assemblies are planned, designed, installed, tested, operated, and maintained to meet the Owner's Project Requirements”.

19

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Types of Buildings in need of Commissioning:

1. Cx of **Existing** Buildings.
2. Cx of **New** Buildings.
3. Cx of **Existing** Buildings that are undergoing **Substantial Renovations**.

*Make a differentiation between the 3 building types and determine additional sensors to incorporate during the design and construction phases to support the Total Building Cx Process (TBCxP) for new and substantially renovated buildings and to facilitate Ongoing Cx moving forward in both bldg types using those new built-in sensors for both monitoring based Cx (MBCx) (& M&V if needed).*

20

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**“Commissioning (or the Commissioning Process):**

[FYI - Old Reference Slides Only]

- **ASHRAE Guideline 1-1996 (The HVAC Commissioning Process)** defines the Cx Process as “*the process of ensuring that systems are designed, installed, functionally tested, and capable of being operated and maintained to perform in conformity with the design intent. In this guideline, commissioning begins with planning and includes design, construction, start-up, acceptance and training, and can be applied throughout the life of the building”.*
- **CA Cx Guide for Existing Buildings** stated that “*Building Commissioning (Cx) is a systematic quality assurance process that spans the entire design and construction process. Building commissioning helps ensure that a new building’s performance meets owner expectations by verifying and documenting that building systems and components are planned, designed, installed, tested, operated, and maintained to meet the owner’s requirements (OPR)”.*

Can remove the old optional FYI slide with the older Definitions, but kept to compare improvement in definition language.

21

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Why **Commissioning**?

22

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Question - Why *Commissioning*?**  
**(*Solid Fuels or Biomass* Htg System Examples)**

1. Ensure correct biomass system *operation, controls and integration* with existing heating systems, energy management and controls system (EMCS), and heat distribution systems.
2. Verify *properly sized boilers* and other support systems.
3. Verify the effectiveness and benefits from *TES/buffering*.
4. Support future quantification of energy and cost savings and, performance validation and *fuel displacement*.

Optional Technology  
Specific Slide Example

23

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Question - Why *Commissioning*?**  
**(*Solid Fuels or Biomass* Htg System Examples)**

1. Facilitate accurate and fair billing with campus style settings that have heat (or chilled water) sale agreements.
2. Use your imagination after your review of the detailed lessons learned slides (shown later in the Detailed Course Stage-II) and how many problems could have been avoided from the beginning "*IF*" proper Cx was implemented from the beginning, which would have been much less costly than the system corrections that were implemented after a significant amount of system troubleshooting and retro-Commissioning.

Optional Technology Specific Slide Example

24

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Answers

350/700/1700 MM BTU

Optional Technology Specific Slide Example

- ① Fully modulating EXHAUST FAN
- ② Water connection: FLOW (with temperature sensor integrated) and THERMAL VALVE (heat exchanger)
- ③ Water connection: RETURN (with temperature sensor integrated)
- ④ CLEANING SHAFT
- ⑤ SERVICE DOORS to maintain the unit
- ⑥ ASH DISCHARGE
- ⑦ HOT AIR GUN
- ⑧ Fully modulating PRIMARY FAN
- ⑨ Fully modulating SECONDARY FAN
- ⑩ STEP-GRATE combustion system
- ⑪ AFTERBURNING with secondary air
- ⑫ Self-cleaning 3-PASS HEAT EXCHANGER
- ⑬ TOP CAP

Illustrations Courtesy of EvoWorld

25
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved

## Q/A - Why **Commissioning?** (General to All Systems) (1 of 2)

- ✓ Provide a “**quality-oriented process** for achieving, verifying, and documenting that the performance of facilities, systems, and assemblies meets defined objectives and criteria” (ASHRAE Guideline 0-2005).
- ✓ The purpose of G0-2005 & 2013 is to “describe the Commissioning Process capable of verifying that a facility and its systems meet the Owner’s Project Requirements (**OPR**)” (ASHRAE Guideline 0-2013) ; & Basis of Design (**BOD**).

## Q/A - Why *Commissioning*? (General to All Systems) (2 of 2)

Optional  
Slide

- ✓ Provide the owner with:
  - ✓ “*Comprehensive quality assurance program*, beginning with the predesign phase of the project, continuing through the design and construction phases, and culminating in sustainable operation by the owner's staff”.
  - ✓ “Commissioning is a programmed series of quality assurance, documentation, and testing activities that are performed specifically to ensure that the *finished facility operates as intended*”
  - ✓ (The Bldg Cx Handbook 2nd Edition).

27

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**How Much does**  
***Commissioning*? Cost?**  
**&**  
**How Much can**  
***Commissioning* Save?**

28

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Q/A - How Much does *Commissioning* Cost?  
(General to All Systems) (1 of 3)**

- ✓ Cx will generally and will definitely add cost to the project's first cost including Cx & TAB, but it will save a lot of energy and money over the building lifecycle cost (BLCC) cost over a 30 to 50 or even a 100 year period.
- ✓ The bottomline is that be aware that the **"the cost of building commissioning is less than the cost of not commissioning your new facilities."** (The Bldg Cx Handbook 2nd Edition).

29

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Q/A - How Much does *Commissioning* Cost?  
(General to All Systems) (2 of 3)**

- ✓ Fact - Building commissioning is important for the success of capital construction projects and should be budgeted for during all project phases.
- ✓ Cx has an attractive return on investment (ROI) and is much better than a CD.
- ✓ Simply, you cannot afford not to Commission.

30

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Q/A - How Much does **Commissioning** Cost? (General to All Systems) (3 of 3)

- ✓ Cx has numerous benefits, one of which is that it helps fill gaps in the needed coordination that generally lacks in many projects and as such communication and coordination is key to the success of this Cx process.
- ✓ Cx supports a well-Integrated Design Process (IDP).

31

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Q/A - How Much Can **Commissioning** Save in terms of energy and other non-energy savings? (General to All Systems) (1 of 4)

In 2004, Lawrence Berkeley National Laboratory estimated \$18 billion per year of potential savings from commissioning throughout the United States. Simply addressing the top 13 faults in commercial buildings alone has a potential savings of **\$3.3 - \$17 billion per year.**

#### Top 13 Faults in Commercial Buildings:

- |   |  |
|---|--|
| 1. Duct Leakage.  | 7. Insufficient evaporator airflow.          |
| 2. HVAC system operates continuously during unoccupied period.  | 8. Improper controls setup / commissioning.  |
| 3. Lighting system illuminating space during unoccupied period. | 9. Control component failure or degradation. |
| 4. HVAC system improperly balanced.                             | 10. Software programming errors.             |
| 5. Improper refrigerant charge.                                 | 11. Improper controls hardware installation. |
| 6. Economizer dampers operating incorrectly.                    | 12. Air-cooled condenser fouling.            |
|   | 13. Valve leakage.                           |

32

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



**Q/A - How Much Can *Commissioning* Save in terms of energy and other non-energy savings? (General to All Systems) (2 of 4)**

- Per US DOE and Pacific Northwest National Lab, A study that included 643 buildings across the U.S. suggests that correcting the deficiencies found during the commissioning process resulted in 16% median whole-building energy savings in existing buildings and 13% in new construction, with payback times of 1.1 years and 4.2 years, respectively.
- It also found that projects that incorporated a thorough commissioning process attained nearly twice the overall median level of savings and five times the savings of the least thorough projects.

33

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Q/A - How Much Can *Commissioning* Save in terms of energy and other non-energy savings? (General to All Systems) (3 of 4)**

- Per US DOE and Pacific Northwest National Lab, Energy savings of new building commissioning can be significant.
- Since they depend on several factors, including building type, location, and the scope of the commissioning process, they are usually presented as a range.
- A comprehensive study found the value of energy savings from commissioning to range from \$0.02 - \$0.19/sqft,
- and the value of non-energy savings resulting from commissioning to range from \$0.23 - \$6.96/sqft, as shown in the table below.

Savings from Commissioning		
Description	Range of Values	Expected Annual Savings for a Theoretical 100,000 sq. ft. Building
Value of Energy Savings	\$0.02 - \$0.19/sq. ft.	\$2,000 - \$19,000
Value of Non-Energy Savings	\$0.23 - \$6.96/sq. ft.	\$23,000 - \$696,000

34

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Q/A - How Much Can *Commissioning* Save in terms of energy and other non-energy savings? (General to All Systems) (4 of 4)**

- Per US DOE and Pacific Northwest National Lab, through proper commissioning these savings can actually increase over time.
- This may seem counterintuitive, but studies have found that when commissioning includes training, and in some cases, installation of permanent metering and feedback systems, improvements in system performance can persist for years after commissioning.
- This finding should reassure building owners that new-construction commissioning can be very durable, and that outcomes will result in savings for the lifetime of the building.

35

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

# Commissioning Process Key Component Definitions

36

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## **Cx Plan:**

- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Cx Plan** as “A document that outlines the organization, schedule, allocation of resources, and documentation requirements of the Commissioning Process”.
- **ASHRAE Guideline 1-1996 (The HVAC Commissioning Process)** defines the **Cx Plan** as “a document defining the commissioning process, which is developed in increasing detail as the project progresses through its various phases”.

## **Cx Authority (or Cx Agent):**

- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Cx Authority (CxA or CA)** as “An entity identified by the Owner who **leads**, plans, schedules, and coordinates the commissioning team to implement the Commissioning Process”.
- **ASHRAE Guideline 1-1996 (The HVAC Commissioning Process)** defines the Cx Agent as “the designated person, company, or agent who **implements** the overall commissioning process”.
- **ASHRAE Standard 202-2013 (Cx Process for Buildings & Systems)** states on Page 27 under Subsection G2.1 that “The primary role of the CxA is to verify achievement of the OPR throughout the project, from Predesign Phase through Occupancy/Operations Phase. The owner could perform the CxA role”.

## **Cx Reporting:**

**ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines:

- The **Cx Process Progress Report** as “A document that details activities completed as part of the Commissioning Process and significant findings from those activities, which is continuously updated during the course of a project. Usually incorporated into the Commissioning Plan as an ongoing appendix”.
- The **Cx Process Report** as “A document that records the activities and results of the Commissioning Process. Usually developed from the final Commissioning Plan with all of its attached annexes”.

## **Testing, Adjusting, and Balancing (TAB):**

- Per **ASHRAE Standard 111-2008 (Measurement, Testing, Adjusting and Balancing of Building HVAC Systems)**,
- The PURPOSE of the standard is “To provide uniform procedures for measurement, testing, adjusting, balancing, evaluating, and reporting the performance of building heating, ventilating, and air-conditioning systems in the field”,
- while the SCOPE Section of the same document states “This standard applies to building heating, ventilating, and air-conditioning (HVAC) systems of the **air-moving** and **hydronic** types and their associated heat transfer, distribution, refrigeration, electrical power, and control subsystems”.

**ASHRAE**, founded in 1894, is a global society advancing human well-being through sustainable technology for the built environment. The Society and its more than 50,000 members worldwide focus on building systems, energy efficiency, indoor air quality, refrigeration and sustainability. Through research, standards writing, publishing, certification and continuing education, ASHRAE *shapes tomorrow's built environment today*. More information can be found at [www.ashrae.org/news](http://www.ashrae.org/news).”

Q. What happens when well-integrated and holistic project development approaches were **not** followed and there was **NO Commissioning?**

List 3 examples.

## **Issues Summary & Highlights of Major Findings** **(Main Categories - Group 1 of 3):**

Optional Technology  
Specific Slide

1. Lack of **TAB** (Test, Adjust and Balance).
2. Lack of **Cx** (Commissioning) process, Issues Logs & **Project Coordination Meetings** .
3. Lack of complete **Control Sequences of Operation**, & Systems **integration**.
4. Inadequate **Designs**, **Drawings** & **Specification** details.
5. Lack of proper **design review by independent 3<sup>rd</sup> party** & Lack of an **Energy Audit** before design.
6. Numerous **system pressurization**, & **HX** (heat exchanger) location & sizing issues.
7. **Pumping, Piping, Valving, VFD** & other **Hydronic issues**.

43

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## **Issues Summary & Highlights of Major Findings** **(Main Categories - Group 2 of 3):**

Optional Technology Specific Slide

8. Incomplete **Pump/Valve Schedules**, & lacking other documentation.
9. No accurate **as-built drawings** *before* & *after* the biomass project.
10. Unclear **Roles and Responsibilities** among project team members during all project phases.
11. Inadequate and Improper **TES (thermal energy storage)** Tanks.
12. Existing Propane/Oil Boiler plant problems were not resolved *before adding* biomass boilers.
13. Bldg **Peak Heat Load Determination** and **Pellet Boiler Sizing** Issues.

44

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Issues Summary & Highlights of Major Findings**  
**(Main Categories - Group 3 of 3):** Optional Technology Specific Slide

14. Issues with **3-way mixing valves** serving biomass boiler & downstream from tank.
15. Lack of enough **BTU meters**, **M&V**, & motor status **CTs**.
16. Lack of **PT Ports** makes it impossible to TAB systems and troubleshoot.
17. ESCO, Design Engineer & Installer lack the necessary biomass (and MEP) system **knowledge & experience**.
18. Issues with **Pellet Boiler reliability** and robustness.
19. Boiler **Container**, BOP (Balance of Plant), Boiler **venting**, & Misc other MEP and/or code issues.
20. ESCO Financial Issues; Oil Prices?; Any one else to blame?
21. Issues with Certain Government Procurement Processes.

45

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Besides the most thorough  
and Comprehensive Four (4)  
Phase Total Building  
Commissioning Process  
(TBCxP), the “other” varying  
types & phases of  
Commissioning include, but  
are not limited to:**

46

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Per the ASHRAE **Cx Guidelines**, Total Commissioning can take place in **4 Phases**:

1. Cx During Pre-Design Phase,
2. Cx During Design Phase,
- 3. Cx During Construction**, and
4. Cx During Occupancy & Operations.

**ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Cx Process** as “A quality-focused process for enhancing the delivery of a project. The process focuses upon verifying and documenting that the facility and all of its systems and assemblies are *planned, designed, installed, tested, operated, and maintained to meet the Owner's Project Requirements*”.

47

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Per the ASHRAE **Cx Guidelines**, the varying types of Commissioning include, but are not limited to:

- 1. Total Building Cx Process (TBCxP) [Inclusive of all 4 Phases].**
2. Continuous Cx Process.
3. Ongoing Cx Process (OCx).
4. Re-Cx.
5. Retro-Cx.
6. Cx Light (or Custom Cx).

48

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



### **Commissioning (Other Types):**

- **ASHRAE Guideline 0-2005 (The Commissioning Process)** defines the **Continuous Commissioning Process** as “A continuation of the Commissioning Process well into the Occupancy and Operations Phase to verify that a project continues to meet current and evolving Owner’s Project Requirements. Continuous Commissioning Process activities are ongoing for the life of the facility. Also see Ongoing Commissioning Process”.
- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Ongoing Commissioning Process (OCx)** as “A continuation of the Commissioning Process well into the Occupancy/Operations Phase to verify that a project continues to meet current and evolving Owner’s Project Requirements. Ongoing Commissioning Process Activities occur throughout the life of the facility; some of these will be nearly continuous in implementation, and others will be either scheduled or unscheduled (as needed)”.

### **Commissioning (Other Types):**

- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Re-Commissioning** as “An application of the Commissioning Process requirements to a project that has been delivered using the Commissioning Process. This may be a scheduled recommissioning developed as part of an Ongoing Commissioning Process, or it may be triggered by use change, operations problems, or other needs”.
- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines **Retro-Commissioning** as “The Commissioning Process applied to an existing facility that was not previously commissioned. This guideline does not specifically address retrocommissioning. However, the same basic process should be followed from Predesign through Occupancy and Operations to optimize the benefits of implementing the Commissioning Process philosophy and practice”.

### **Commissioning (Other Types):**

- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines the **Basis of Design (BoD)** as “A document that records the concepts, calculations, decisions, and product selections used to meet the Owner’s Project Requirements and to satisfy applicable regulatory requirements, standards, and guidelines. The document includes both narrative descriptions and lists of individual items that support the design process”.
- **ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process)** defines **Owner’s Project Requirements (OPR)** as “A document that details the functional requirements of a project and the expectations of how it will be used and operated. These include project goals, measurable performance criteria, cost considerations, benchmarks, success criteria, and supporting information. (The term Project Intent is used by some owners for their Commissioning Process Owner’s Project Requirements.)”.

### **Commissioning (Other Types):**

#### **USGBC - LEED New Construction (NC) Reference Guide Energy & Atmosphere (EA) Credits **Prerequisite 1: Required Point** -**

**Fundamental Commissioning of the Building Energy Systems;**  
Completion of the following commissioning process activities by the Design & Cx Team:

1. Designate *qualified & independent* **CxA entity** to lead, review & oversee completion of Cx process activities.
2. Owner document the Owner Project Requirements (**OPR**).
3. Design Team develop the Basis of Design Document (**BOD**).
4. CxA develop **Cx Plan**.
5. Design Team to Develop & Incorporate **Cx Requirements** into Construction Documents (**CDs**) i.e., in Specs.
6. Project Team **Implement Cx Plan**.
7. **Verify installation & performance** of commissioned systems.
8. Complete summary **Cx Report**. (Results reported directly to owner)

### **Commissioning (Other Types):**

**USGBC - LEED NC Ref. Guide Energy & Atmosphere Credits: *Optional Credit* - Enhanced Commissioning of the Building Energy Systems.** Intent:

“Begin the commissioning process *early* during the design process and execute additional activities *after* system performance verification is completed”. Completion of *more* Cx process activities by Design & Cx Team:

1. Satisfy all Fundamental Cx Requirements (See earlier slide).
2. CxA complete mid-construction stage Cx Design Review of **OPR & BOD** then,
3. **back-check** necessary updates completed in subsequent design submission.
4. CxA review **contractor submittals** of commissioned systems for compliance with OPR & BOD.
5. Design Team to Develop **System Manual** for operating staff to understand and operate all commissioned systems.
6. Verify completion of all operating personnel (and occupants) **training** completed.
7. CxA **10 month operations review**.

# Commissioning Team Members & Determination of their Roles & Responsibilities

## Determination of Roles & Responsibilities

1. Customer, Owner, or Applicant.
2. Project Manager of the Owner (**PM**).
3. Construction Manager (**CM**).
4. Architect, Design engineer of record, (MEP, **E/A** or A/E Firm), with special focus on Mechanical and/or HVAC.
5. General Contractor (**GC**).
6. Mechanical Contractor (**MC** or **MEP**).
7. Test, Adjust & Balance Contractor (**TAB** or **T&B**).
8. Commissioning (**Cx**) Authority (**CxA**), or Cx Oversight Consultant.
9. Specialty Sub-contractors (especially in large projects) such as:
  10. Controls Contractor (**CC**) - EMCS Vendor, System Integration Contractor, low voltage contractor.
  11. Electrical Contractor (**EC**).
  12. M&V Agent, or **M&V** Consultant, or M&V Contractor.
  13. Boiler Manufacturer.
  14. Boiler Testing & Boiler Cx Contractor.
  15. Thermal Energy Storage Tank Manufacturer/Vendor.
  16. Other Equipment Manufacturers / Suppliers such as HX, Silo, Valves, Underground Pipes, etc.
  17. Local authorities or authorities having jurisdiction over the project (needed for obtaining certain permits and/or to ensure compliance with all local codes, rules and regulations),
  18. ESCO (Energy Services Company).
  19. Funding Agency or Financing Agency.
  20. Utility: Fuel supplier & Pellet Supplier.
  21. Specialty Consultants (in certain complex projects).

Very Important Slide

55

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## The Commissioning Scoping Meeting (1 of 2)

1. The CxA (through the GC or CM) will schedule, plan and conduct a Cx scoping meeting w/ the **Entire Cx Team**.
2. At the meeting, **Cx parties are introduced**, Cx process is reviewed, and management and reporting lines are determined.
3. Construction Phase **Cx Plan** is reviewed, process questions are addressed, **lines of reporting and communication** are determined, and the work products list is discussed.
4. Other discussion topics include the general list of **each party's responsibilities**, responsibility for development of startup plans for each piece of equipment, and the proposed commissioning schedule.

56

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## The Commissioning Scoping Meeting (2 of 2)


5. Meeting outcome is that each team member will have a better understanding of the Cx process and of their **Specific Roles and Responsibilities**.
6. Meeting also provides the CxA with additional information required to finalize the Cx Plan, including the anticipated Cx Sch & the varying forms.
7. GC, CM or CxA keep notes from Mtg and distribute them to each team member.
8. Prior to this meeting, the CxA is given, by the GC (or CM or A/E), all drawings and specifications and the construction schedule by trade.

## The Core of the Construction Phase Cx Process:

Prefunctional Checklists  
(PFCs)  
&  
Functional Performance  
Testing (FPTs)

# [1] Prefunctional Checklists (PFCs)

## Prefunctional Checklists (PFCs) - (1 of 4)

- Document that equipment and systems are properly installed and operational so that functional performance testing may proceed without unnecessary delays.
- Each piece of equipment receives full prefunctional checkout by the installing contractor.
- **No sampling strategies are allowed.**
- Pre-Functional Performance Testing ***must be***  ***successfully completed prior*** to formal functional performance testing of equipment or subsystems.

## Prefunctional Checklists ([PFCs](#)) - (2 of 4)

- Prefunctional checklists are primarily static inspections and procedures to prepare the equipment or system for initial operation (e.g., proper fan belt tension, valve installed in proper direction, proper oil level provided, labels affixed, gauges in place, sensors calibrated, etc.).
- However, some PFC items entail simple testing of the function of a component, a piece of equipment or system (such as measuring the voltage imbalance on a 3-phase pump motor, verifying that a fan rotates in the proper direction, etc.).
- ***The word prefunctional refers to “before” functional testing.***

61

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Prefunctional Checklists ([PFCs](#)) - (3 of 4)

- Prefunctional checklists augment and are combined with the manufacturer’s start-up checklist and plan.
- Contractors typically already perform some, if not many, of the prefunctional checklist items the commissioning authority will prescribe.
- However, unfortunately, not all contractors document in writing the execution of these checklist items.
- Put all Prefunctional checklists developed for this project in [Appendix C](#) of the Cx Plan.

62

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Prefunctional Checklists (PFCs) - (4 of 4)

- Procedures must be documented in writing by the installing technician using the standard checklists developed and/or co-developed by the CxA as well as the manufacturer's start-up checklist and/or a satisfactory/comprehensive combination of both following whatever is more stringent and best for the project.
- The CxA does not witness much of the prefunctional checklist execution, except for testing of larger or more critical pieces of equip and some spot-checking of minor equipment.

## [2] Functional Performance Testing (FPTs)



## Functional Performance Testing (FPTs) - (1 of 3)

- Functional performance testing (FPT) is the dynamic testing of systems (rather than just components) under full operation.
- Ex.: The variable speed district loop Glycol pumps are tested interactively with the individual building's heat exchanger modulating terminal control valves to verify that pump speed ramps up and down to maintain differential pressure at setpoint.
- More complex dynamic testing for example will also involve the pellet boiler sequencing and integration with the operation of the oil and propane boilers in the individual building MERs.

65

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Functional Performance Testing (FPTs) - (2 of 3)

- Generally, systems are tested under various modes, such as during low and intermediate heating (or cooling) loads, shoulder seasons, high loads, component failures, unoccupied (or setback) mode, varying outside air temperatures, power failure, etc.
- The systems are run through all of the control system's sequences of operation and components are verified to be responding as the sequences state.

66

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Functional Performance Testing (**FPTs**) - (3 of 3)

- The commissioning authority develops (and/or co-develops) the functional test procedures in a sequential written form, and then coordinates, oversees and documents selected actual testing;
- All testing is performed by the installing contractor or vendor under the guidance (and/or the direction) of the CxA.
- Put the project specific functional test forms available to date in **Appendix D**, while make a note that some others may still be forthcoming if not ready yet.

## Suggested Issues & Resolution Log (or Deficiencies Log) Detailed Layout/Table & Minimum Content Requirements

## Issues & Resolution Log (Deficiencies Log) - (1 of 3)

Pyramid EES  
Engineering & Construction Services

**Issues and Resolution Log** [ Updated as of MM/CO/YEAR ]

Facility or Project Name: \_\_\_\_\_  
 Building or Location: \_\_\_\_\_  
 Construction Authority (CA or CAI): **Pyramid Energy Engineering Services, PLLC (Pyramid EES)**

Issue Item #	System or Equipment & Location	Equipment Type <sup>1</sup>	Project Phase <sup>2</sup>	Date Identified	Initiated by	Issue Description or Deficiency	Issue Class <sup>3</sup>	Responsible Contractors	Recommended Actions	Status (Open or Closed)	Date Resolved <sup>4</sup>	Response by (Name)	Explanation of Correction and Other Notes or Comments	Note #
<p><b>Notes:</b></p> <p>1. Equipment type: Mech, Elec, Ltg, Plumbing, MEP, BOP, Piping, TES Tank, Pellet Storage and Conveyance, BMS, M&amp;V, Boiler Venting/Chimney (Flue Products), Boiler Room Ventilation, General, Building Envelope/Enclosure or M&amp;V, Enduses, Structural, Site, Safety, etc.</p> <p>2. Project Phase: Construction, TAB (0 - 99) then Cx Phases: PFC = prefunctional (100 - 199), S = spot check of prefunctional testing, FPT = functional testing (200 - 299), TD = Trend data (300 - 399), M&amp;V (400 - 499), etc.</p> <p>3. Issue Classes: Energy, IEQ, O&amp;M, and Maintenance (E&amp;M, Measurement and Verification - M&amp;V, TAB, Safety, Procedural, Proper Storage of Materials &amp; Equip, Scheduling and Construction Management (CM, PM, QA/QC, Change Orders, Access, Aesthetics, etc.</p> <p>4. Date Resolved: Indicate the date that no issues remain on the construction schedule.</p> <p><b>Disclaimer:</b> CA (or CAI) assumes no responsibility for how the material in these Cx Issues and Resolution Logs may be utilized by users. The users assume full responsibility for any and all liability that may arise from any reference to, or use of, this material. This log is not intended to capture all issues during construction and Cx, as it captures only what CA and Owner had observed during site visits/inspections. It is the contractors, CM, GC and Design Engineer's full responsibility to ensure that any other unobserved issues are addressed and the project is built and controlled in compliance with the construction documents and following all best practices.</p> <p style="text-align: center;"><small>© 2019 EES</small></p> <p style="text-align: center;">Use the space below if additional space is needed for <b>NOTES</b> and reference the systems and page numbers from previous in this <b>Issues and Resolution Log</b>.</p>														

## Issues & Resolution Log (Deficiencies Log) - (2 of 3)

- |   |   |
|---|---|
| <ol style="list-style-type: none"> <li>1. Issue or Item #</li> <li>2. System or Equipment &amp; Location</li> <li>3. Equipment Type<sup>1</sup></li> <li>4. Project Phase<sup>2</sup></li> <li>5. Date Identified</li> <li>6. Initiated by</li> <li>7. Issue Description or Deficiency</li> <li>8. Issue Class<sup>3</sup></li> <li>9. Responsible Contractors</li> <li>10. Recommended Actions</li> <li>11. Status (Open or Closed)</li> <li>12. Date Resolved<sup>4</sup></li> <li>13. Response by (Name)</li> <li>14. Explanation of Correction and Other Notes or Comments</li> <li>15. Note #</li> </ol> | <ol style="list-style-type: none"> <li>1. <b>Equipment Type:</b> Mech, Elec, Ltg, Plumbing, MEP, BOP, Piping, TES Tank, Pellet Storage and Conveyance, BMS, M&amp;V, Boiler Venting/Chimney (Flue Products), Boiler Room Ventilation, General, Building Envelope/Enclosure, Structural, Site, Safety, etc.</li> <li>2. <b>Project Phase:</b> Construction &amp; TAB (0 - 99); then Cx Phases: PFC = prefunctional (100 - 199), S = Spot-Check of prefunctional testing, FPT = functional testing (200 - 299), TD = Trend Data (300 - 399), M&amp;V (400 - 499), etc.</li> <li>3. <b>Issue Classes:</b> Energy, IEQ, O&amp;M, M&amp;V, TAB, Safety, Procedural, Proper Storage of Materials &amp; Equip, Scheduling CM, PM, QA/QC, Change Orders, Access, Aesthetics, etc.</li> <li>4. <b>Date Resolved:</b> Indicate the date issue was resolved or its correction was verified.</li> </ol> |
|---|---|

### Issues & Resolution Log (Deficiencies Log) - (3 of 3)

- Disclaimer - CA (or CxA) assumes no responsibility for how the material in these Cx Issues and Resolution Logs may be utilized by users. The users assume full responsibility for any and all liability that may arise from any reference to, or use of, this material. This log is not intended to capture all issues during construction and Cx as it captures only what CxA and Owner had observed during site visits/inspections. It is the contractors, CM, GC and Design Engineer's full responsibility to ensure that any other unobserved issues are addressed and the project is built and controlled in compliance with the construction documents and following all best practices.
- -- END OF LOG --
- Use the space below if additional space is needed for NOTES and reference the systems and page numbers from previous in these Issues and Resolution Logs:

## Commissioning Schedule & Typical General Scheduling Issues & Warnings

## Cx Scheduling & Issues & Warnings

The following sequential priorities shall be followed:

1. Equipment is not “temporarily” started (for heating or cooling) until pre-start checklist items and all manufacturers’ pre-start procedures are completed and moisture, dust and other environmental and building integrity issues have been addressed.
2. **Functional testing is not begun until prefunctional checklists, start-up and TAB are completed** for a given system (this does not preclude a phased approach).
3. The controls system and equipment it controls are not functionally tested until all points have been calibrated and pre-functional testing completed.
4. TAB is not performed until the controls system has been sufficiently functionally tested by the CC and approved by the GC (or CM), A/E and CxA for TAB work.

Very Important Slide

73

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Overview of the Construction Phase Commissioning Process

Keep Slide  
for Stage-II  
Course

74

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Overview of Commissioning Process - (1 of 4)

1. Cx during construction ***begins*** with a “commissioning scoping meeting”, conducted by the CxA preferably within 60 to 90 days of the beginning of construction, where the Cx process is reviewed with Cx team members.
2. Additional meetings will be required throughout construction to plan, coordinate, schedule future activities, and resolve problems. The additional meetings will be scheduled as needed by the GC (or CM).
3. Equipment documentation shall be submitted to the CxA during normal submittals, including detailed start-up procedures.
4. The CxA develops (and/or oversees the development of) prefunctional checklists (PFC) and submits blank forms to the GC (or CM) for assignment and distribution to the subcontractors. Subcontractors shall complete PFCs during the start-up process.

Keep Slide for Stage-II Course

75

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Overview of Commissioning Process - (2 of 4)

5. In general, the checkout and performance verification proceeds from simple to complex; from component level to equipment to systems and intersystem levels. Prefunctional checklists must be completed and returned to the CxA ***before*** functional testing begins.
6. Contractors, under their own direction and/or preferably via schedule coordination with the GC (or CM), execute and document the prefunctional checklists (PFC) and perform start-up and initial checkout. The GC or CM (and at times the CxA for selected equipment) document the completion of the PFCs and startup procedures according to the approved plans and using the PFC forms provided by the CxA and whatever other sources of documentation and forms they desire to use for best documentation. This may require the presence of the CxA as a witness upon start-up of selected equipment.

Keep Slide for Stage-II Course

76

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Overview of Commissioning Process - (3 of 4)

7. CxA develops (and/or oversees the development of) specific equipment and system functional performance test (FPT) procedures and forms.
8. FPTs are executed by the contractors and the appropriate forms are properly completed under the guidance (and/or the direction) of the CxA. The Contractors and/or CM/GC properly and thoroughly document the functional performance test results using the appropriate forms provided by the CxA for the CxA's review. Any deficiencies are recorded by the CxA (and/or the Contractors or CM) on the **Commissioning Issues Log**.
9. Items of non-compliance in material, installation, or setup are corrected at the contractor's expense, and the deficient system will be retested.
10. CxA (and CM) review O&M documentation for completeness.

Keep Slide for Stage-II Course

77

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Overview of Commissioning Process - (4 of 4)

11. Contractors submit to the CxA through the GC (or CM) training plans, and the CxA reviews and pre-approves training plans before training by the contractors can proceed. The GC (or CM) coordinates any training provided by the contractors. The CxA verifies that training was completed as required.
12. Seasonal or other deferred testing is conducted, as specified or required.
13. CxA prepares a final report to document the results of the commissioning process.
14. CxA returns to the site approximately 8 to 10 months into the 12-month warranty period to review current building and system operation with facility staff and address the any conditions or outstanding issues related to the owner's project requirements.
15. CxA develops a re-commissioning management manual for the owner, as needed.

Keep Slide for Stage-II Course

78

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)


© (2019) Pyramid EES. Rights reserved

# Key Cx Phase Process Flow Charts



Very Important Slides

---


79
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved









**Figure 5-4: Functional Performance Test (FPTs) Forms Development**



**Figure 5-5: Functional Performance Test (FPT) Submittal Map**





# Suggested Commissioning Plan Detailed Outline

86 Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a) © (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (1 of 9)

- Glossary of Terms and Abbreviations
- Objectivity and Related Affiliations
- Notice
- Acknowledgments
- Table of Content
  
- **Section 1.0 - Project Overview:**
- 1.1 Background & Project History.
- Recap on OPR (& BOD).

87

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (2 of 9)

- 1.2 - Description of Building Energy Systems & Features:
  - All Buildings (Age, Envelope, Lighting, HVAC Systems, Schedules, etc.).
  - The Boiler Room.
- 1.3 - Key Abbreviations and key Definitions:
  - Commissioning (or the Commissioning Process)
  - Cx Plan
  - Cx Authority (or Cx Agent)
  - Testing, Adjusting, and Balancing (TAB)
  - [See Definitions presented earlier in the Slides]
- 1.4 - Purpose of the Commissioning Plan.
- 1.5 - Cx Scope (& 1.6 - List of Commissioned Systems).
- 1.7 - Spec Sections (Referenced for supporting Cx).
- 1.8 - Spec Relevant Notes.

88

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (3 of 9)

- **Section 2 - General Building Information**
  - Includes but not limited to Bldg & Proj Description, Location, Building Type, Floor Area, Number of Stories, Owner, Construction Period, Construction Schedule [See Appendix B], Cx Schedule [See Appendix B].
- **Section 3 - Commissioning Team Members**
  - Table 3-1 includes all Commissioning Team Members complete contact Info, Agency Name, Member Name, Title, Address, email, Phones (landline and Mobile), web page).
- **Section 4 - Roles and Responsibilities**
  - 4.1 - Cx Team Members
  - 4.2 - General CxA Management Plan
  - 4.3 - General Description of Team Member Roles

89

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (4 of 9)

- **Section 5 - Commissioning Process**
  - 5.1 Overview....
  - 5.2 Commissioning Scoping Meeting
  - 5.3 Final Commissioning Plan - Construction Phase
  - 5.4 Site Observation (& Site visits schedule)
  - 5.5 Misc. Meetings (to be scheduled as needed)
  - 5.6 Misc. Management Protocols & flow of Docs.)
  - 5.7 Progress Reporting (& Cx Issues & resolution log)
  - 5.8 Initial Submittals and Documentation
    - 5.8.1 Standard Submittals
    - 5.8.2 Special Submittals, Notifications and Clarifications

90

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (5 of 9)

- **Section 5 - Commissioning Process (Cont.)**
- **5.9 Prefunctional Checklist (PFC), Tests & Start-Up:**
  - 5.9.1 Overview
  - 5.9.2 Start-up Plan
  - 5.9.3 Execution of Checklists and Start-up
  - 5.9.4 Deficiencies and Non-Conformance
  - 5.9.5 Testing and Balancing
  - 5.9.6 Controls Checkout Plan
- **5.10 Functional Performance Test (FPT) Development and Verification Procedures:**
  - 5.10.1 Overview
  - 5.10.2 Scope of Testing
  - 5.10.3 Development Process
  - 5.10.4 Testing Plan Overview and Schedule

91

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (6 of 9)

- **Section 5 - Commissioning Process (Cont.)**
- **5.11 Execution of Functional Testing Procedures**
  - 5.11.1 Coordination and Scheduling
  - 5.11.2 Deficiencies and Retesting
  - 5.11.3 Facility Staff Participation
  - 5.11.4 Sampling
- 5.12 O&M Manuals and Warranties
  - 5.12.1 Standard O&M Manuals
  - 5.12.2 Commissioning Record
  - 5.12.2a O&M Manuals General Format
- 5.13 Training and Orientation of Owner Personnel
- 5.14 Warranty Period

92

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Cx Plan Detailed Outline - (7 of 9)

- **Section 6 - Written Work Products**
  - 6.1 Overview of Work Products [Described later in PP Slides]
  - 6.2 Commissioning **Final Report** [Suggested Detailed Outline shown later]
  
- **Section 7 - Commissioning Schedule**
  - 7.1 General Scheduling Issues
  - 7.2 Commissioning Schedule [Include in Appendix B]

## Cx Plan Detailed Outline - (8 of 9)

- **Section 8.0 - Appendices**
  - Appendix A - Owner's Project Requirements (OPR) Docs
  - Appendix B - Construction Schedule
  - Appendix C - **Prefunctional Checklists (PFC)** (Can be Editable & Executable).
  - Appendix D - **Functional Performance Testing (FPT)** Requirements and Test Forms (Can be Editable and Executable)
  - Appendix E - Selected Spec Sections calling for Cx, TAB, and Varying Test Requirements (based on the Contract Documents)

## Cx Plan Detailed Outline - (9 of 9)

- **Section 8.0 - Appendices (Cont.)**
  - Appendix F - Selected Construction Phase Application/Implementation forms in support of both the Prefunctional and the Functional Performance Testing.
  - Appendix G - Other Appendices TBD as needed.
- **End**
  - Review Notes and Other Comments by Cx Plan Users.

## Suggested Commissioning Report Outline



## Commissioning Report Outline - (1 of 5)

Cx report to be prepared by CxA and shall include, but is not limited to:

- **Executive Summary**, project overview, & relevant project background, & concise list of Exec level findings, conclusions & recommendations. All to fit within a few pages.
- Generally, the use of photographs and other graphic illustrations is encouraged.
- List of project participants and their roles.
- Building and energy system descriptions.
- Overview of commissioning and testing scope.
- A general description of the testing and verification methods used.

The above is to be followed by a detailed description of the testing and verification methods used coupled with necessary illustrations.

## Commissioning Report Outline - (2 of 5)

For each piece of commissioned equipment, the report shall contain the disposition of the commissioning authority regarding the adequacy of the equipment, documentation and training meeting the contract documents in the following areas:

- Equipment meeting spec.
- Equipment installation.
- Functional performance and efficiency.
- Equipment documentation and design intent.
- Operator training.

### Commissioning Report Detailed Findings - (3 of 5)

- Present results of the Cx project in more detail; keeping in mind that the main focus of Cx effort was ensuring systems & equipment operate efficiently and reliably so predicted savings and/or fuel displacements are achieved.
- Confirm (as applicable and as practicable) that the CxA has also reviewed submittals and inspected systems and equipment to determine if they meet minimum requirements set forth by the project initial Technical Feasibility Study [Dated], the design documents [Dated] and the OPR and BOD [Dated] and any other relevant resources.
- All Deficiencies and/or outstanding items shall be reported as detailed below:

99

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Commissioning Report Details - (4 of 5)

Cx report shall also address the following items:

- All outstanding non-compliance items shall be specifically listed.
- Recommendations for improvement to equipment or operations, future actions, commissioning process changes, etc. shall also be provided.
- Each non-compliance issue shall be referenced to the specific functional test, inspection, trend log, etc. where the deficiency is documented.
- The functional performance and efficiency section for each piece of equipment shall include a brief description of the verification method used (i.e., manual testing or BAS trend data analysis) and include observations and conclusions from the testing.
- CxA to produce graphs from the data to make trends more apparent so that system operation issues can be more easily diagnosed. Graphical data displays are key to successfully illustrate the completion of the testing and operation of the tested equipment and systems.

100

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Commissioning Report Details & Appendix - (5 of 5)

During reporting on the above items, include any Appendix type or lengthy material into well organized and tabbed Appendices. This can include but is not limited to:

- Selected parts of the additional trend data plots beyond what was necessary in the body of the report.
- Detailed Cx Issues & Resolution Logs.
- Also include the complete project contact list for the record.
- Additional equipment submittals that were provided during the Cx process, but were not necessarily part of the bid Docs.
- Any project awards or certificates that are worth sharing.
- Final Cx Plan & PFCs (by now should have already been submitted to Owner, GC (or CM)) do not have to be part of the final report, but will be stored in the Cx Record Manual, that will be referenced as part of the Cx report.

# PDH Questions / Answers for Assessment of Learning

Select Only Five (5) Q/A for  
Stage-I Course and keep the  
rest for Stage-II Course

## PDH Questions / Answers - (Q/A 1)

- **Q1** - Commissioning is just a quick site visit in the afternoon from 2 to 4 PM, with no need for any preparation or any forms or any formalities; Let's get it over with, quickly and just move on. True or False?
- **A1** - False.

## PDH Questions / Answers - (Q/A 2)

- **Q2** - Per the ASHRAE Cx Guidelines, what are the primary Phases for the Commissioning process?
- **A2** - [1] Cx During **Pre-Design Phase**, [2] Cx During **Design Phase**, [3] Cx During **Construction**, and [4] Cx During **Occupancy & Operations**.
- It is definitely not a quick visit for casual system testing.

## PDH Questions / Answers - (Q/A 3)

- **Q3** - What is one of the best definitions for the Cx Process, and why?
- **A3** - Per ASHRAE Guideline 0-2005 & 2013 (The Commissioning Process), it defines the Cx Process as “A quality-focused process for enhancing the delivery of a project. The process focuses upon verifying and documenting that the facility and all of its systems and assemblies are **planned, designed, installed, tested, operated,** and **maintained** to meet the **Owner's Project Requirements**”.

105

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 4)

- **Q4** - Is the **Cx Plan, PFCs, FPTs, proper execution of all forms, Issues Logs** then **Cx Report** enough for conducting Cx? True or False?
- **A4a** - Yes and No!
- **A4b - Yes;** If you are only doing Construction Phase Cx.
- **A4c - NO;** If the intention is a comprehensive Cx process during all project phases starting from:
  - [1] Cx During Pre-Design Phase,
  - [2] Cx During Design Phase,
  - **[3] Cx During Construction,**
  - and [4] Cx During Occupancy & Operations.
  - Therefore, phase 3 only does not suffice for a comprehensive process; & phases 1, 2 & 4 must be done.

106

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 5)

- **Q5** - How many members are in the Commissioning Team and how often do they need to communicate?
- **A5** - Varies anywhere from 6 to over 20 depending on the project size and complexity and the number of disciplines involved.
  - CxA regularly communicates with all members of the commissioning team, keeping them apprised of commissioning progress and scheduling issues through memos, progress reports, etc.
  - At a minimum, there should be webinars (and/or site visits) every 2 weeks by the GC, PM (and CxA is present) to discuss and address all project issues during construction and not wait till the PFC and FPT stages.
  - Early CxA involvement and coordination with all team members is a must.

107

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Keep some of the following slides in Stage-I as reference material only (and/or provide a quick overview of selected important slides depending on audience level);

Otherwise, move them under Separate Stage-II.

108

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

# PDH Questions / Answers for Assessment of Learning

Only Five (5) Q/A: Q1 to Q5 were presented  
in Stage-I Course.

Keep Q6 to 11 for Stage-II Course.

## PDH Questions / Answers - (Q/A 6)

- **Q6** - Can the GC start **FPT** before **PFC** (and why yes or no)?
- **A6** - The word prefunctional refers to **before** functional testing.
  - Functional Performance Testing must be successfully completed **prior to** formal functional performance testing of equipment or subsystems.
  - PFCs basically document that equipment and systems are properly installed and operational so that functional performance testing **may proceed without unnecessary delays**.

## PDH Questions / Answers - (Q/A 7)

- **Q7** - What are the most important 3 items you gathered from this presentation (besides having lunch)?
- **A7** - Must have a full Cx team and their roles and responsibilities are well define upfront.
  - Complete all PFCs well before FPTs
  - Maintain and stay on top of Issues & Resolution Logs (deficiencies log) during ALL project phases and do a great job.
  - Take Cx seriously for the future of your project and educate the Owner of the importance of Cx.

111

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 8)

- **Q8** - List a few of the known barriers impeding the implementation of the proper Cx process in numerous projects and how to avoid them?
- **A8a** - Lack of knowledge of the multiple benefits of Cx.
- Lack of Cx budgets.
- Bad value engineering, where Cx can be removed from proj!
- Lack of requiring Cx by law (i.e., Cx may not be part of building code) in some areas.
- Lack of customer and project team education.
- Lack of qualified Cx contractors.
- Lack of good project leadership in the first place.
- **A8b** - Educate, Educate, Educate all team members (starting with owner) & budget for Cx like any other important project item.

112

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



## PDH Questions / Answers - (Q/A 9)

- **Q9** - What are a few of the most important ASHRAE guidelines and standards that best define and describe the commissioning process?
- **A9** - ASHRAE Guideline 0-2005 & 2013 (**The Commissioning Process**).
- ASHRAE Guideline 1-1996 (**The HVAC Commissioning Process**).
- ASHRAE Guideline 1.1 - 2007 (**HVAC&R Technical Requirements for the Commissioning**).
- ASHRAE Standard 202-2013 (**Cx Process for Buildings & Systems**).
- ASHRAE Standard 111-2008 (**Measurement, Testing, Adjusting and Balancing of Building HVAC Systems**).
- ASHRAE Guidelines 11-2009 (**Field testing of HVAC controls components**).
- See other Guidelines issues by the Associated Air Balance Council (AABC) or more specifically AABC Commissioning Group (ACG).

113

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 10)

**Q10** - What are most knows organizations issuing Cx Certifications?

**A10** - ASHRAE, AABC/ACG, AEE, BCA/BCxA/BCCB, Univ. of Wisconsin-Madison, NEBB.

- **[1] ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers**
  - BCxP - Building Commissioning Professional Certification
  - CPMP - Commissioning Process Management Professional
- **[2] AABC = Associated Air Balance Council**
- **ACG = AABC Commissioning Group**
  - CxA - Certified Commissioning Authority (Certification issues by ACG)
  - CxTs - Certified Commissioning Technicians (Certification issues by AABC or ACG)
  - EMP - Energy Management Professional (Certification issues by ACG)
- **[3] AEE = Association of Energy Engineers**
  - CBCP - Certified Building Commissioning Professional
- **[4] BCxA = Building Commissioning Association**
- **BCCB = Building Commissioning Certification Board**
  - CCP - Certified Commissioning Professional
  - ACP - Associate Commissioning Professional
  - BEMP - Building Energy Modeling Professional Certification (Certification issues by ASHRAE & is a prerequisite for the CCP certification)

114

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 10 Cont.)

**Q10** - What are most knows organizations issuing Cx Certifications?

**A10** - ASHRAE, AABC/ACG, AEE, BCxA/BCCB, Univ. of Wisconsin-Madison, NEBB.

- **[5] University of Wisconsin-Madison.**
  - Descriptions of Certifications for Educational Achievement:
    - QCxP - Qualified Commissioning Process Provider.
    - BECxP - Building Enclosure Commissioning Process Provider.
    - CxA+BE - Commissioning Authority + Building Enclosure.
  - Descriptions of Certifications for Educational Achievement Plus Project Experience:
    - CxAP - Commissioning Process Authority Professional
    - CxM - Commissioning Process Manager
    - CxTS - Commissioning Process Technical Service Provider
    - GCxP - Green Commissioning Process Provider
- **[6] NEBB - National Environmental Balance Bureau.**
  - BSC CP - Building System Commissioning Certified Professional
  - BSC CxCT - Building System Commissioning Certified Technician
  - CxPP - Commissioning Process Professional Certified Professional
  - RCx-EB CP - Retro-Commissioning of Existing Buildings Certified Professional.

115

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 10 Cont.)

**Q10** - What are most knows organizations issuing Cx Certifications?

**A10** - ASHRAE, AABC/ACG, AEE, BCxA/BCCB, Univ. of Wisconsin-Madison, NEBB.

- **[7] NIBS - National Institute of Building Sciences (Defines the Total Building Cx Process).**
  - NCBC - National Conference on Building Commissioning.
- **[8] SMACNA - Sheet Metal & Air Conditioning Contractors' National Association.**
  - SMACNA HVAC System Commissioning Manual.

116

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## PDH Questions / Answers - (Q/A 11)

- **Q11** - Per the ASHRAE Cx Guidelines, what are the varying types of Commissioning and why are there that many?
- **A11a** - [1] Total Building Cx Process (TBCxP).
- [2] Continuous Cx Process.
- [3] Ongoing Cx Process (OCx).
- [4] Re-Cx.
- [5] Retro-Cx.
- [6] Cx Light (or Custom Cx).
- **A11b** - Cx Type variations depend on whether the building is **existing** or **new**, or if it has been commissioned in past, and if that past Cx was adequate, etc.

117

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

# Suggested Commissioning Management Protocols

Keep Slide  
for Stage-II  
Course

118

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Commissioning Management Protocols - (1 of 2)

	Issue	Protocol
1	For requests for information (RFI) or formal documentation requests:	The CxA goes first through the GC (or CM) <i>then</i> through the contractors.
2	For minor or verbal information and clarifications:	The CxA goes directly to the informed party.
3	For notifying contractors of deficiencies:	The CxA documents deficiencies through the GC (or CM), but may discuss deficiency issues with contractors prior to notifying the GC (or CM). The A/E is also informed of deficiencies identified by the CxA.
4	For scheduling <b>functional tests</b> :	The CxA schedules functional tests through the GC (or CM).
5	For scheduling commissioning meetings:	The GC (or CM) selects the date, in coordination with the CxA, and makes necessary arrangements for the meeting.
6	For making a request for significant changes:	The CxA has no authority to issue change orders.

119

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Commissioning Management Protocols - (2 of 2)

	Issue	Protocol
7	For making small changes in specified sequences of operations:	Generally, the CxA may <i>not</i> make changes to specified sequences without approval from the A/E.  In limited situations, however, the CxA may recommend making small sequences of operations changes to improve efficiency or control or to correct deficiencies, through the responsible contractor, but shall document the change and provide all changes of specified sequences to the CM, GC and A/E.  Responsible suggestions shall be made preferably in consultation and coordination with the GC (or CM), the CC and the major equipment maker impacting and/or impacted by the sequence of operation changes as applicable).
8	Contractors disagreeing with requests or interpretations by the CxA shall:	Attempt to resolve with the CxA first. Then work through the GC (or CM), who will work with CxA directly to resolve the situation.
9	For scheduling training:	The CxA may provide input for and do some coordination of training, but does not do the scheduling; Scheduling done through the GC (or CM).

120

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

# Suggested Written Work Products

Keep Slide  
for Stage-II  
Course

121

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Written Work Products (1 of 3)

	Product	Developed By
1	Final commissioning plan	CxA
2	Meeting minutes	CxA, GC (or CM)
3	Commissioning schedules	GC (or CM) with Contractors and CxA
4	Equipment documentation submittals	GC (or CM) and Contractors
5	Sequence clarifications	CC, Boiler manufacturer, Hydronics Consultant, A/E, or a combination of the above, as needed.
[6]	<u>Prefunctional</u> checklists (PFC)	CxA (& with support from GC (or CM), CC, Subcontractors and the Boiler Manufacture, as needed).
[7]	Start-up and initial checkout plan	GC and Contractors (compilation of existing documents)
[8]	Start-up and initial checkout forms filled out	GC (or CM) and Contractors

Keep Slide  
for Stage-II  
Course

122

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Written Work Products (2 of 3)

	Product	Developed By
9	Final TAB report	TAB Subcontractor
10	Commissioning Issues Log (deficiencies)	CxA
11	Commissioning Progress Record	CxA
12	Deficiency reports	CxA (& also based on executed functional test forms completed by contractors).
[13]	Functional performance tests (FPC) and forms	CxA (& with support from GC (or CM), CC, Subcontractors and the Boiler Manufacture, as needed).
[14]	Executed functional test forms	GC (or CM) and Contractors

Keep Slide  
for Stage-II  
Course

123

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Written Work Products (3 of 3)

	Product	Developed By
15	O&M manuals	GC (or CM) and Contractors
16	Commissioning record manual	CxA
17	Overall training plan	GC (or CM) with Contractors; and reviewed by CxA
18	Specific training agendas	GC (or CM) with Contractors; and reviewed by CxA
19	Final commissioning report	CxA
20	Recommissioning Management Manual	CxA
21	Miscellaneous Cx-related approvals	GC (or CM), A/E and CxA

Keep Slide  
for Stage-II  
Course

124

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

# Suggested Project Close-out Documents

125

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Project Completion & Closeout Docs (1 of 3)

1. Provide all **Equipment Warranty** documentation.
2. Provide all equipment **Installation**, and **O&M Manuals**.
3. Provide all as-installed and complete **Equipment Submittals** as part of the O&M Manuals.
4. Define all related **O&M Roles and Responsibilities** moving forward between the **Service Contractor**, **Boiler Maker**, and the **Site Owner** in terms of scopes and schedules.
5. Secure **Service Agreements** to support the site in the future at a minimum with the **Mechanical Service Contractor** and preferably with the **Controls Contractor**. Ensure all agreements have enough detail in terms of scope details and frequent of services.
6. Provide **As-Built Mechanical Drawings** & as-built/updated equipment & pump & HX schedules.
7. Provide **As-Built Wiring (& Control) Diagrams**.
8. Provide **As-Built Architectural & Structural Drawings** & all project related drawings not include above.

126

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Project Completion & Closeout Docs (2 of 3)

9. Provide **As-Built Control Sequences of Operation (SOO)** especially after many control changes were done during system Cx. Ex. Clearly spell out how the pellet boilers are controlled using external commend as opposed to the tank upper and lower Temperature sensors for on/off signals to the pellet boilers.
10. Provide updated & final as-built **Controls Submittals** including all sensors covering all hardware, all software, all updated drawings & all details.
11. Provide written Standard Operating Procedures (**SOPs**) and access credentials for all information needed to successfully run the plant BMS, acquire data from the BMS and from all Monitoring based Cx equipment for Ongoing Cx and verification of as intended operation of all systems.
12. Provide the updated and **As-Built Test and Balance (TAB) Report**.
13. Secure a reliable and quality **Supply Source of Pellets**.

127

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Project Completion & Closeout Docs (3 of 3)

14. Completion of adequate customer **Controls Training**.
15. Completion of adequate customer **Boiler Training**.
16. Completion of adequate customer other **BOP Training** and system components (water softener, glycol system, chemicals, etc.).
17. **Training Manuals** for all training(s) for entire system and all BOP.
18. Attach clear **Equipment & Pipe Labels** that indicate flow direction everywhere for your flag ship projects.
19. Verify **full sets of soft & hard copies** of the items listed above are provided & easily accessible to those needing them for proper system operation, maintenance, trend logging, ongoing Cx, and project demonstration for success stories.
20. Include **Other Documentation** as need such as all proj permits, inspection records, financial and legal project paperwork, or items of project relevance not included above, etc.

128

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



## Project Completion & Closeout **Cx** Docs (1 of 1)

1. **Cx Plan** (Updated as necessary).
2. **OPR & BOD** (Updated as necessary).
3. **Training Manual** for entire system and all BOP.
4. **System O&M Manual** for entire system & all BOP.
5. **Issues and Resolution Log** (Closeout & completed).
6. Final **Cx Report**.
7. Convene **Lessons Learned Workshop** (Optional, but strongly recommended).
8. **Other TBD** as needed on case by case basis.

Suggested List Courtesy of ASHRAE Cx Resources


## Glossary of Terms, Abbreviations & Acronyms

See end of slides for the full Glossary of Terms, Abbreviations & Acronyms.



## Q/A

*Thank you all for Attendance and Participation*

Khaled A. Yousef, PE, CEM, CDSM, LEED AP, GBE  
 Principal Energy Engineer / Founder  
 Pyramid Energy Engineering Services, PLLC (Pyramid EES)   
 30 Karner Road #12369, Albany, NY 12212, USA  
[Khaled.A.Yousef@PyramidEES.com](mailto:Khaled.A.Yousef@PyramidEES.com)  
 +1 (518) 221-7382  
[www.PyramidEES.com](http://www.PyramidEES.com)

Energy Efficiency & Sustainability | Optimization | Modeling | Technical & Design Assistance  
 | Master Planning | LEED Support | Commissioning | CHP | Biomass | R&D

*Thank you*  *NYSERDA* *for your support*

Suggested  
**End** of the Stage-I Cx  
 Course

**End**

133

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Formal **Beginning** of the in-depth Stage-II Cx Course;

(Satisfactory Completion of Stage-I is a Prerequisite **before** beginning Stage-II).

134

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

In-depth PFCs, FPTs,  
Lessons Learned & other  
detailed Slides and  
Pictorial Examples for  
Stage-II Only

135

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Detailed Review and  
Hands-on Examples of  
Prefunctional Checklists  
(PFCs)

[Appendix C]

136

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)


© (2019) Pyramid EES. Rights reserved

Switch from PP Slides to [PFCs](#)  
Appendix-C XLS or PDF Files  
during that Section of the  
Detailed Course

# Detailed Review and Hands-on Examples of Functional Performance Testing (FPTs)

## [Appendix D]

Switch from PP Slides to FPTs  
Appendix-D XLS or PDF Files  
during that Section of the  
Detailed Course




Start with a Brief Overview of Biomass Heating Systems during a brief Section of the Detailed Course Stage-II only as a refresher over the next few slides;

However, the audience should have reviewed the other detailed “*Introduction to Properly Sized Advanced HELE (High-Efficiency, Low-Emission) wood-pellet based Biomass Boiler Heating Systems and the Renewable Heat New York (RHNY) Governor’s Initiative*” as a pre-requisite to fully understand the forthcoming in-depth lessons learned section primarily caused by lack of system Cx during different phases of a few selected earlier projects.

142 Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a) © (2019) Pyramid EES. Rights reserved

Outdoor Wood Pellet Silo






Biomass Boiler inside shipping container.


143
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved

## Thermal Energy Storage (TES)

### 2 Gal/1,000 Btu/hr requirements



85,000 Btu/hr (25 kW) pellet boiler.  
170 gal TES by requirements, but  
119 gal (non ASME) is allowed for  
 boilers  $\leq$  25 kW.



Large 2,500 gal (2 x 1,250 gal) TES

144
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved



### Introduction to RHNY (& CGC) Suggested System Layout and System Requirements

**Proper Pellet Boiler Sizing:** Commercial pellet boilers should be sized to  $\leq 60\%$  of the design heating load as it will capture the majority of the heating season and promote higher performance.

Earlier Version Slide for System Layout

It should be noted that some of the diagrams in this presentation may be updated in the future as they examine the most optimal buffer tank location at the end of the hydronic loop vs. at the begin of the loop.

Arrow denotes the use of either a pellet fired or cord wood boiler. Also denotes using an auxiliary boiler before or after the buffer tank.

Diagram Courtesy of John Siegenthaler, P.E., Appropriate Designs

---

145 Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a) © (2019) Pyramid EES. Rights reserved

### Introduction to RHNY - Suggested System Layout (1 of 3)

It should be noted that some of the diagrams in this presentation may be updated in the future as they examine the most optimal system component locations and may vary based on site specific conditions.


Updated Slide

Diagram Courtesy of PBSSIM.

---

146 Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a) © (2019) Pyramid EES. Rights reserved

Introduction to RHNY - Suggested System Layout (2 of 3)



It should be noted that some of the diagrams in this presentation may be updated in the future as they examine the most optimal system component locations and may vary based on site specific conditions.

Updated Slide


Diagram Courtesy of PBSSIM.

147

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Introduction to RHNY - FYI - System Layout (3 of 3) with no TES. This is not recommended - Must use TES.



It should be noted that some of the diagrams in this presentation may be updated in the future as they examine the most optimal system component locations and may vary based on site specific conditions.

Updated Slide

Diagram Courtesy of PBSSIM.

148

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Pellet Plants in NYS - 500 kTon per year - now with bulk delivery! & is increasing



Photos Courtesy of NYSERDA

149

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Question - List Major Biomass System Components

### Boiler:

- Combustion Chamber/Fire Door.
- Fuel Feeding System (Primary Auger and Stoker Auger).
- Combustion Air Supply.
- Boiler Controls, O<sub>2</sub> lambda sensor.
- Heat Exchanger/fire tubes.
- Exhaust/breaching/vent/barometric relief damper.
- Fuel igniter/ash cleaning/ash removal.
- Boiler Controller, Log File and Remote access capabilities.

### Other BOP and Heating System:

- Fuel Storage Silo/Bunker.
- Fuel Conveyor/Auger System.
- EMCS or Building Automation System.
- Water Connections, Primary/Secondary Pumping, Controls Valves, Check Valves.
- Flue and Chimney and proper Boiler room venting.
- Post combustion gas treatment (cyclone, ESP, filter).

150

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

Answers - Part 1 of 2

**ACT Bioenergy™ Boiler with fuel auger**

1. Rotating arm to feed fuel to auger
2. Auger drive shaft
3. Main fuel bin auger
4. Main fuel bin auger channel
5. Auger drive motor
6. Flap valve to prevent burn-back
7. Ultrasonic probe to measure fuel in intermediate fuel bin
8. Intermediate fuel storage bin
9. Agitator to prevent fuel bridging
10. Burner fuel feeding auger
11. Emergency extinguishing system
12. Hot air ignition blower
13. Primary, secondary and tertiary blower motors with VFDs
14. Control panel box
15. Control panel display
16. Burner ring (primary gasification zone)
17. Rotating ash grate
18. Secondary and tertiary air introduction rings
19. Ash collection bin
20. Flap valve actuator to bypass boiler tubes during start-up
21. Double insulated heat exchanger
22. Rotating turbulators to clean boiler tubes
23. Turbulator drive motor
24. Exhaust fan with VFD

Illustrations Courtesy of ACT Bioenergy

151
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved

Answers

350/700/1700 MM BTU

- ① Fully modulating EXHAUST FAN
- ② Water connection: FLOW (with temperature sensor integrated) and THERMAL VALVE (heat exchanger)
- ③ Water connection: RETURN (with temperature sensor integrated)
- ④ CLEANING SHAFT
- ⑤ SERVICE DOORS to maintain the unit
- ⑥ ASH DISCHARGE
- ⑦ HOT AIR GUN
- ⑧ Fully modulating PRIMARY FAN
- ⑨ Fully modulating SECONDARY FAN
- ⑩ STEP-GRATE combustion system
- ⑪ AFTERBURNING with secondary air
- ⑫ Self-cleaning 3-PASS HEAT EXCHANGER
- ⑬ TOP CAP

Illustrations Courtesy of EvoWorld

152
Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)
© (2019) Pyramid EES. Rights reserved

Optional  
Slide

# Brief Boiler Sizing Examples Section

(Only 2 Optional Slides)

## *Alternative methods*

153

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Sizing Ex 4 - Biomass Boiler Sizing - ADM4

Optional  
Slide

Examination of boiler sizing for the existing 2.74 million Btu/hr oil fired boilers total input rating as well as the new high efficiency wood pellet boiler: First Made-in-NY ACT biomass boiler (0.5 million Btu/hr single boiler).

- Total Existing Boiler Output Cap = 2,190,000 Btu/hr (@ 80% eff)
- Total Combined Building Floor Space = 51,000 ft<sup>2</sup>
- Total Boiler Normalized Output Capacity / ft<sup>2</sup> = **43 Btu/h/ft<sup>2</sup>**
- Estimated Peak Campus Load = **1,080,000 Btu/hr**
- Estimated Peak Campus Load Normalized = **21 Btu/h/ft<sup>2</sup>**
- Recommended Biomass Boiler Cap = **500,000 Btu/hr (150 kW)**
- Recommended Biomass Boiler Cap Normalized = **10 Btu/h/ft<sup>2</sup>**
- Installed TES = 1,500 Gallons (approximate volume of chilled water loop; however, take this with extreme caution as it was not thermally stratified vertical storage)



154

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Sizing Example 5 - WC5



Bulk wood-pellet storage bin that was creatively built out of a re-purposed shipping container that also supports a solar-thermal hot water system.

Optional  
Slide



- New and efficient building - LEED Certified.
- Building area = 54,000 ft<sup>2</sup>
- Estimated Peak Building Load = ~ **18 to 23 Btu/h/ft<sup>2</sup>**  
Normalized
- Installed Biomass Boiler Cap = **1,700,000 Btu/hr (500 kW)**
- Installed Biomass Boiler Cap = **31.5 Btu/h/ft<sup>2</sup>**  
**Examine if and why it is oversized?**
- Many Good Lessons learned:
  - Avoid oversizing.
  - Install TES/Buffer tank.
  - Use modulating propane fired boilers as auxiliary heat sources and auxiliary fuel, during very low loads and as peak load supplement, etc.
  - Controls integration and boiler sequencing,
  - CO Off gassing precautions.



155

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**In-depth Review of the  
 Issues Summary & Highlights  
 of Major Findings under 3  
 Main Categories:  
 Group 1 of 3 (Items 1 to 7)  
 Group 2 of 3 (Items 8 to 13)  
 Group 3 of 3 (Items 14 to 21)**

156

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## **Issues Summary & Highlights of Major Findings** **(Main Categories - Group 1 of 3):**

Required Technology  
Specific Slide.

1. Lack of **TAB** (Test, Adjust and Balance).
2. Lack of **Cx** (Commissioning) process, Issues Logs & **Project Coordination Meetings** .
3. Lack of complete **Control Sequences of Operation**, & Systems **integration**.
4. Inadequate **Designs**, **Drawings** & **Specification** details.
5. Lack of proper **design review by independent 3<sup>rd</sup> party** & Lack of an **Energy Audit** before design.
6. Numerous **system pressurization**, & **HX** (heat exchanger) location & sizing issues.
7. **Pumping, Piping, Valving, VFD** & other **Hydronic issues**.

157

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## **Issues Summary & Highlights of Major Findings** **(Main Categories - Group 2 of 3):**

Required Technology Specific Slide.

8. Incomplete **Pump/Valve Schedules**, & lacking other documentation.
9. No accurate **as-built drawings** *before* & *after* the biomass project.
10. Unclear **Roles and Responsibilities** among project team members during all project phases.
11. Inadequate and Improper **TES (thermal energy storage)** Tanks.
12. Existing Propane/Oil Boiler plant problems were not resolved *before adding* biomass boilers.
13. Bldg **Peak Heat Load Determination** and **Pellet Boiler Sizing** Issues.

158

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Issues Summary & Highlights of Major Findings (Main Categories - Group 3 of 3): Required Technology Specific Slide.

14. Issues with **3-way mixing valves** serving biomass boiler & downstream from tank.
15. Lack of enough **BTU meters**, **M&V**, & motor status **CTs**.
16. Lack of **PT Ports** makes it impossible to TAB systems and troubleshoot.
17. ESCO, Design Engineer & Installer lack the necessary biomass (and MEP) system **knowledge & experience**.
18. Issues with **Pellet Boiler reliability** and robustness.
19. Boiler **Container**, BOP (Balance of Plant), Boiler **venting**, & Misc other MEP and/or code issues.
20. ESCO Financial Issues; Oil Prices?; Any one else to blame?
21. Issues with Certain Government Procurement Processes.

159

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [1] Issues & Observations - (TAB):

1. Lack of complete Heating Plant **TAB** w/ pellet boiler flows, oil boiler flows, both sides of HX (loop side and building side).
2. **Incomplete & one-time TAB does not suffice**; Projects needed an **iterative TAB process** till completion.
3. **As-built TAB (and as-built drawings verifications)** were seriously lacking despite being core prerequisites to making subsequent plant decisions.
4. Lack of **PT Ports** made it impossible to TAB the systems and troubleshoot.
5. Pressure taps & balancing valves should've been installed **downstream** of pumps for future test & balance (not upstream).



160

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



## [2, 3 & 10] Issues & Observations - (Cx & Controls):

1. Lack of System **Commissioning (Cx)** during **ALL** project phases from design to construction & operation; See Cx Definitions at end of slides.
2. Lack of complete/detailed **issues & resolution logs**. Can also be called events log or deficiencies log.
3. Lack of complete **Control Sequences of Operation** and **System Integration** covering the operation and controls of the entire **hybrid heating plant**, pellet boilers, TES tanks, all pumps, valves, oil/propane boilers; Also need to address **oil/propane boiler cycling**.
4. Proper implementation of control sequences require an **interactive programming process** to revisit the control sequence impacts after their initial settings, then adjust and reprogram as necessary, in an iterative manner until stable system operation is attained. This could take a few weeks of back and forth (or seasons) until completed successfully; not a one day trip!



161

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## [4, 5 & 6] Issues & Observations - (HX & Operating Pressures):

1. Lack of design engineer and/or ESCO understanding of the **Pellet Boiler's 185 Deg F max leaving temp and 30 psig max operating pressure (i.e., the boiler's pressure relief valve setting)**.
  - b) Incorrect 200 Deg F leaving temperature "assumption" resulted in incorrect HX sizing.
  - c) Exceeding 30 psig necessitated adding a HX.
2. Installation of **Undersized HX (heat exchangers)** between district loop side & building side caused by incorrect loop temperature assumptions & incorrect temperature drop assumptions everywhere (on both sides of the HX).
3. To reduce pellet boiler pressure, **HX was incorrectly installed** in between boiler & TES tank, as opposed to in between the tank & the loop. Expensive relocation needed to serve as proper pressure break.



162

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**[4, 5 & 6] Issues & Observations - (System Operating Pressures):**


1. **Suspected pump cavitation, system pressurization and trapped air issues were caused by P-2 district loop pump installed on incorrect pipe on the loop return pipe as opposed to the loop supply pipe.**
2. P-2 suspected to pull air from negative pressure areas/connections upstream of district loop pipe due to incorrect P-2 location.
3. Lack of pump schedule and lack a thoughtful pressure gradient curve to estimate suction and discharge pressures before installations.
4. See drawing on next slide.



163

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



164

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

[5 & 7] Issues & Observations -  
(Oil/Propane Boiler Plant Piping &  
Re-Piping):

1. **Do not** rush and proceed with biomass heating projects without a full understanding of the *existing* heating plant & DHW heating in terms of as-builts, piping, valving, controls, and the original design intent. Determine if enhancements or corrections are needed well **before** moving forward with the biomass boilers' addition. **Must Plan ahead & Cx during Proj. Planning.**
2. Ex - Suggestion - Re-pipe small oil boiler for year-round use as opposed to only Summer DHW Use. This will reduce large oil boiler cycling in winter after adding the pellet boiler. Do the proper loads analysis and do the necessary control modifications.



165

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

[5 & 7] Issues & Observations -  
(Oil/Propane Boiler Plant Piping  
& Re-Piping):

1. Suggestion - Injecting the pellet loop heat in the return header leading to the oil/propane boilers (**upstream** of propane boilers) is a safe and simple means of injecting pellet heat into an existing distribution (as opposed to injecting **downstream**);
2. However, that being said, ensure that there are piping provisions to **bypass** the existing oil/propane boilers when they are not needed, otherwise, they act as radiators and wastefully dissipate heat into the boiler room and up the stack.



166

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [11] Issues & Observations - (TES Tanks):

1. Use of ineffective, inadequate, small, **short and fat 4-pipe TES** (with a poor aspect ratio) caused tank to be ineffective for storage; Therefore, it was suggested using an alternative **2-pipe, vertically stratified TES tank with more storage capacity** and better aspect ratio; At a minimum, investigate if the existing 4-pipe tank can be re-piped/converted into a 2-pipe tank. Additionally, evidence of tank valve leaks were observed.
2. Verify tanks have **horizontal perforated diffusers** or preferably **diffuser trays** so the entering and leaving water does not upset the tank thermal stratification.
3. The entering/leaving bottom TES tank pipes were not low enough and the upper TES tank pipes were not high enough. They should have been as far away from each other as possible.
4. Inadequate as-built documentation of whether the tank diffusers or trays were installed, and if yes, if they were properly installed.




167

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### TES Evolution (Original 4-Pipe Configuration vs. Modern 2-Pipe Configuration)




168

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Improved Low Velocity Diffusers in Modern 2-Pipe Tank Configurations to attain better thermal stratification?**



Diagrams Courtesy of John Siegenthaler, P.E., Appropriate Designs

169

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**Consider using internal flow diffuser plates rather than sparge tube diffusers. The plates would likely be lower cost, and offer less flow resistance.**




Diagram Courtesy of John Siegenthaler, P.E., Appropriate Designs

170

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

- Up to this point, there were enough slides for the short 54-minute presentation averaging 2-minutes per slide (+ 6 minutes for Q/A); however, past this point, it will need more time than the 1.0 hr available.
- More slides are included later for reference only for attendees who desire to review more lessons learned past this point; A high level overview will be presented; unless the 2.0 hr is available.....
- Go to the Take Home Messages & Next Steps section, then to the Questions to conclude on time.

171

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [3. 7 & 11] Issues & Observations - (Pumping, VFD Pumping, 3-Way mixing valves, & TES):

1. Lack of pump controls and flow balancing upstream and downstream of TES Tank. Ensure all pumps are well controlled to utilize the true benefits of a 2-pipe tall tank. Lack of pump controls can upset the tank stratification if either side over pumps and if **flows between the P-1 primary boiler loops and P-2 secondary district loop were not balanced**. Typically, P-1 is fixed speed, but P-2 is preferably variable speed to more accurately respond to load, but unfortunately this was not always followed, causing problematic system operation and ineffective use of the thermally un-stratified TES tank.
2. Uncontrolled, **unintentional, and excessive operation of the pellet boiler pump** after the pellet boiler de-energizes caused an inverted temperature profile in the vertical TES tank and dissipated a good part of the thermal energy (that was supposed to have been stored in the tank) into the boiler room via the pellet boiler shell through radiation, convection, and stack losses. This was caused by a software issue from the pellet boiler.



172

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [11 & 14] Issues & Observations - (3-Way valves, VFD Pumping, & TES):

1. The **3-way mixing valve** serving the biomass boiler suffered from operational and control issues including both types: self-contained thermostatically controlled or electrically actuated/controlled (by the pellet boiler). Issues included but were not limited to valve stem issues, valves wired in reverse, valves installed in opposite direction, valves did not completely close or fully seat (causing unintentional bypassing), etc.
2. Valve operational issues observed at multiple installations, but issues were not documented in a clear issues log and a thorough testing, Cx and TAB process was not followed from the beginning of project.
3. Verify operation of the **3-way mixing valve** between the tank and the system as part of TAB. Hot water resets will be more important with pellet boiler projects and will expand the effective BTU storage capacity and full utilization of the TES tank. At times, the desired valve was not even installed; The design engineer originally planned for it, but the ESCO requested it be removed or installed did not install it.



173

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [4] Issues & Observations - (Drawings & Specs):

1. Project **Specifications** were not provided.
2. However, when specs were provided, they were problematic, for example:
3. **Lengthy project specifications lacked the detail and needed focus** regarding the biomass heating system. At times, specs were several hundred pages long, but without the needed focus on the biomass project; Strongly caution against unthoughtful copy and paste from existing spec templates!
4. Additionally, lengthy standard specs from a wood chip project were mistakenly used in a wood pellet project; for example, a cyclone was not installed in the pellet project despite being mentioned in the wood chip project specs.
5. This was just a brief example of using improper specs, but there were many other examples.

174

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

#### [4 & 5] Issues & Observations - (Drawings & Specs):

1. **Drawings** lacked the biomass heating system design details with specific focus on the pellet boiler connection to TES and the tank full details. Unclear system schematics that lacked the necessary detail were not acceptable and caused numerous problems later on during construction and later during system operation.
2. Lack of proper **design review by independent 3<sup>rd</sup> party** in the past caused numerous issues that went unidentified during all project phases. All should have been addressed in a timely manner before building the biomass project. It should be a design-build process and not a build-design process.
3. Design engineering firm selection should consider whether they have enough central plant, hydronics, controls, Cx and biomass system experience; and a good relationship with TAB contractors to facilitate any back and forth TAB process.

175

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

#### [17] Issues & Observations - (Level of Experience):

1. Lack of the **necessary biomass knowledge** and system-specific needs by both the Design Engineer and the Controls Contractor. Both relied on the ESCO's biomass and non-biomass heating systems experience, which later proved to be inadequate.
2. **Lack of ESCO experience, project leadership, and knowledge about what it takes to commence a proper design through implementation/Cx/Start-up process to attain reliable operation.** This led to removing Cx and TAB details from project documents with no understanding of the consequences of such removals. Additionally, there was no understanding of the necessary in-depth energy and engineering knowledge of the BOP and MEP support systems needed to attain a reliable biomass heating system installation, controls and operation.
3. Mechanical contractor blindly implements parts of the design and does a good job with what appears to be quality construction and quality workmanship, but unfortunately with no thought whether the design was appropriate or not. Despite the contractors' general MEP and HVAC experience, the **mechanical contractor lacked biomass heating system experience** and relied on the engineers' drawings (& lacking specifications).

176

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



### [18] Issues & Observations - ([Unreliable Operation](#)):

1. Biomass boilers **operational and reliability issues** were reported, and manufacturer appeared to have been addressing issues expeditiously; however, a detailed **issues and resolution log** was not provided.
2. Replaced **broken turbulator**, as needed. Requested certain manufacturer to explain what caused it to break and how to avoid that in the future.
3. There is currently ongoing efforts to enhance the **reliability of other boiler sensors and components** and get better error messages and complete boiler Installation & O&M Manuals & full documentation.
4. Repeated failures of boiler **burner rings** caused some pellet boilers to be down for extended periods of time until parts were installed by the manufacturer.

Note - **Biomass boilers unreliable operation** vs. frequent **short cycling** were two separate problems caused by different reasons ranging from both boiler maker reliability vs. BOP and controls related issues. Those two should not be confused.

177

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [18] Issues & Observations - ([Unreliable Operation](#)):

1. **O<sub>2</sub> sensor issues (lambda sensors?)**. Were detailed calibration, setup and Cx procedures followed?
2. **3-way mixing valve** issues were faced in multiple sites.
3. Sight glass and **photo cell** issues (near the front panel).
4. **Vacuum sensor** issues in multiple sites.
5. Needed to **reboot** the boiler several times to get the updated firmware/boiler control updates and the data logging on thumb drive resumed and to ensure boiler resumes desired normal operation.
6. **Pellet fill level sensor** malfunction (or becomes dusty and requires cleaning).
7. **Igniter malfunction** - Needed replacement.
8. **Unreliable internet connection** prevented boiler maker from remote access for viewing, receiving alarm notifications, & troubleshooting.



178

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## [2, 10, 17 & 20] Issues & Observations - (ESCO Experience, Project Communication & Roles & Responsibilities):

1. **ESCO Financial**, cash flow issues and project interruptions.
2. Issues from ESCO Financial pressures caused QC issues and reduction in project scope, sometimes in an unthoughtful manner, like removing some of the necessary control valves, TAB and Cx from project scope.
3. Did ESCO have adequate knowledge of negative impacts of what was being cut from the scope of work?
4. **Poor communication and relationship** between the ESCO and the General Contractor.
5. **Poor communication and relationship** between the Customer and the ESCO.
6. **Lack of the necessary project coordination meetings** during all project phases.
7. Is the **drop in oil prices in 2015/2016 to blame? NO** - Although oil prices had some negative contribution to the problems, there were numerous other factors above that made certain projects dysfunctional.
8. Oil Prices? Prices may not stay that low for a long time, but we cannot predict the future.
9. Unclear **Roles and Responsibilities** among multiple project entities and during all project phases.

179

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## [19] Issues & Observations - (The Boiler Container):

1. **Questionable quality of pellet boiler container construction**. Multiple leaks observed, both originating from inside the container and from the outside shell.
2. **Backup ceiling-mounted electric unit heaters (~ 3.0 kW) did not energize as intended during the dead of winter 2015/2016** when the pellet boiler system was down and the container (including the pellet boilers and the TES tank) were stone cold. Luckily it was filled by PG30 that should not freeze. **Boiler & BOP needed to be tested after exposure to extreme cold and investigate if that added to the gasket leaks in the container as well.**
3. Missing actuator for container combustion intake air louvers (and/or container ventilation louvers) may have been deliberately eliminated by the ESCO. This presented a freeze hazard in winter if boilers are down for extended duration during frigid weather with no backup electric heat.
4. Another site had a dysfunctional actuator for boiler room air intake grill so the same freezing concern was shared since the expansion tank was sitting right next to the cracked open grill.
5. No floor drains in container. Should it be rubberized floor?
6. Why un-insulated boiler container in the Northeast? Examine the use of insulation, but available space presents challenges if insulated from the inside, but okay if insulated from the outside for an additional cost.



180

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [19] Issues & Observations - (**Boiler Venting**):

1. Gap in the stainless steel (SS) chimney; Soot (and fly ash) observed inside the boiler container.
2. Black smoke residue was observed on top of the 2 metal chimneys; indicative of incomplete combustion; Cycling, etc.?
3. Verify there was no pellet boilers excessive cycling if user or CxA has access to the historic log file and/or BTU meter data; however, no data was log provided.
4. Should include CO alarm response as part of the future control sequences.
5. Address barometric relief damper inconsistency between specs vs. implementation. Suggest use of a better quality positive pressure seal SS barometric relief damper due to multiple benefits.
6. As biomass boilers take away load from the oil/propane boilers, examine the application of **brick chimney inner lining** to address potential condensation issues after the pellet plant starts to operate. Stainless steel lining preferred.



181

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [13] Issues & Observations - (**System Sizing**):

1. In Proj A - Inaccurate building areas leading to misleading **normalized peak heat load calculations**.
2. Proj A - Inaccurate Peak Heat Load Calculations - The installed **1.4 million Btu/h** biomass boiler container had a correct size, despite the ESCO's incorrect normalized peak heat load determination (based on incorrect building areas) resulting in **93.1 Btu/h/sqft (2,700,000 Btu/h / 29,000 sqft)**. The 93.1 was **triple** the peak heat load of **27.6 Btu/h/sqft (2,200,000 Btu/h / 79,635 sqft)** that was independently estimated by Pyramid EES.
3. Proj B - Unclear **bdg. peak heat load** determination due to no baseline measurements & no TAB; causing peak load assessment to widely vary from 1.1 to 2.3 million Btu/h depending on the calc. method used (Bldg Area = 57,261 sqft). This impacts the sizing of the future biomass boilers and the 3<sup>rd</sup> oil boiler claimed to be needed for redundancy, but no TAB evidence was submitted to substantiate the needed redundancy claims.

182

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [13] Issues & Observations - (**System Sizing & EEMs**):

1. Size new pellet boilers based on updated building heat load determinations, and preferably after factoring in EEM savings that were identified in the energy audit. EEM suggestions from real projects include but are not limited to:
  2. Apply DCV controls on future Unit Ventilators to reduce building loads.
  3. Control OA dampers.
  4. Complete numerous building envelope upgrades.
  5. Ensure that the future controls scope provides for better zoning (and space comfort) than existing as project converts from pneumatic controls to DDC.
  6. Consider low-temperature heat emitters when specifying new radiators, UVs & RTUs.
  7. Implement heating hot water resets as part of the new controls using the 3-way mixing valve at the plant and the new VFD pump.
  8. Generally, implement any other EEMs and capital projects that reduce building heating loads *before* finalizing system sizing (use holistic project approach).
  9. Question - Can unreliable and uncalibrated Energy Models be used to reliably predict EEMs savings in an energy audit? Ans. Absolutely NO, but why?
10. **STOP - Do not put the cart before the horse and do not rush in any biomass boiler projects before conducting an ASHRAE Level-II or-III energy audit.**


183

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [3, 7, 8 & 9] Issues & Observations - (**Drawings, Hydronics & Controls**):

1. The ESCO treating the pellet boiler container as a **black box** and marginalizing the roles of the Design Engineer and the Controls Contractor were major project setbacks.
2. Incomplete **Pump/Valve Schedules in drawings**.
3. No accurate **as-built drawings** other than an incomplete hand sketch.
4. Moving forward, verify that the heat generated from the oil boilers does not get inadvertently directed back into the storage tank. Hydronic & controls detail were needed.
5. Examine the different scenarios of controlling the biomass boilers; from the **tank upper and lower temperature sensors** or from the loop temperatures vis external command.
6. Could not verify pellet boiler manufacturer claims that the pellet boilers can modulate down to a certain point (say 30%). Requested data to illustrate such operation, but no logged data was provided.
7. Unclear about the required heating hot water distribution temperatures to satisfy the existing heat emitters at the building at varying OATs.



184

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [15] Issues & Observations - (M&V Misc):

1. Lack of enough **BTU meters** & other **M&V instrumentation**. Only 1 BTU meter deployed at district P-2 (downstream from TES tank to the loop), but no with no M&V data to clearly show how much heat was delivered to each of the district buildings, HX effectiveness, etc.
2. Thermal wells were shown on the TES tank diagram, but thermocouples were not inserted in 3 out of 5 of them (the middle ones). More vertical sensors would support better evaluation of the TES tank operation.
3. Lack of M&V Data Points - More M&V data points and trend-logged data were needed "*You cannot manage what you do not measure*".
4. Loss of M&V data occurred due to simple reasons such as a power outage; At a minimum, use a UPS to keep the data collection system running for several hours to prevent such data loss, and check the data periodically to reduce unpleasant surprises.
5. Ensure proper installation of ultrasonic flow transducers & temperature sensors on pipe surfaces & in wells to obtain accurate BTU meter data. More can be elaborated on this topic separately in an M&V training.
6. Data collection using the boiler built-in microprocessor panels, Modbus and remote access presented challenges depending on the boiler manufacturer; Not all manufacture provided such built-in features.



185

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [15] Issues & Observations - (Misc M&V & Sensors):

1. Sub-metering of Selected Loads (served by oil, propane or electricity) supports a better baseline development, boiler sizing process, and better understanding and analysis of multiple end uses; Besides space heating and DHW heating needs, there is also the commercial kitchen cooking, dishwashing, laundry, sterilization, incineration, etc.
2. Carefully set the BMS to Trend log the needed M&V Data points; in some cases, despite having capable EMS, they were not set for trend logging.
3. Protect the data collection equipment through proper shields and clear signs to prevent from accidentally tampering with it causing loss of data, (especially if any construction activity is surrounding the data collection system).
4. Include local OAT as part of M&V, is it part of the existing BMS now?
5. Verify accuracy of pressure gauge displays.
6. Uncertain how deep the tank thermal wells were. The deeper the better (minimum of 6" desired).
7. Thermal wells lacked the application of proper thermal grease.
8. BTU meter flow transducers lacked the application of proper acoustic coupling compound.

186

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [19] Issues & Observations - (**Insulation**):

1. Tank insulation: Removable blankets are preferred over permanent fiberglass or spray foam insulation. In either case, maintain  $\geq R-24$  insulation. In some projects, it was too late to examine insulation options as the less expensive fiberglass insulation was already applied. First cost was a major factor in selecting the use of permanent fiber over removable blankets; Blankets were needed for better tank access to pipes and fittings and for tank troubleshooting when leaks were observed.
2. Verify that the existing heat trace controls do not run unnecessarily and in a wasteful manner if OAT is above freezing. Heat trace elements were located on the above ground hot water loop pipes between the boiler container and the building.
3. Why use an un-insulated boiler container in the Northeast? Examine additional insulation, but available space may present a challenge. Standard shipping containers were typically tight both horizontally & vertically.



187

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### [19] Issues & Observations - (**Misc**):

1. DHW tank was set at 140 Deg F with no setback.
2. O&M Staff Training needs.
3. Ensure proper coordination between the cyclone fan and the induced draft fan speeds.
4. Observed damaged pellets in the day hopper and a lot of pellet dust, this was an indication of why boiler operation problems and some error messages were received. Change pellet suppliers was necessary.
5. Cover exposed USB port at the pellet boiler (& M&V Equipment) to protect from dust.
6. Verify calculations if the 25 to 36 Ton silo is undersized for extended pellet boiler operation during frigid weather conditions.
7. Suggestion - Empty the pellet silo before the summer to prevent potential interior condensation that can damage the pellets and cause issues with operation of the auger assembly. Additionally, properly seal the bottom of the silo to prevent moisture entry and impacts from splashing rain water. Not following the above caused the pellets to absorb moisture, get wet, clog the auger, and prevent the boiler from first operation in the fall.

188

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

General Issues Summary & Observations - (*Despite the many Lessons Learned, Is there hope? - Ans. Yes, but how, see below*):

1. The above conglomerate of issues resulted in a need for requesting and generating an as-built set of drawings, TAB, numerous design then construction corrections, complete Cx and plant sequences, etc. The hybrid plants could not run reliably in its current state, which is why the site went back to solely operating the oil or propane boilers (Until the system makeover project was completed to address most of the identified issues, which was a very expensive repair and correction process).
2. The above represents a summary of what was observed during site visits and subsequent analyses, but **there could be more issues that were not identified**. This was likely due to lacking biomass boiler test and startup information at some sites. Also, the operation and modulation of the pellet boiler itself has not been verified under all load conditions and for operation periods that are long enough to illustrate reliable pellet boiler operation.
3. Despite the above issues, there is a path for corrections (a system makeover) if the customer is willing to invest in system corrections by addressing the above items and as summarized in the Section Titled "**Take Home Messages & Next Steps**".
4. General Continuing Education and Training (M&V, Cx, TAB, and Hydronics) were needed for all team members. This has to be done correctly and there were no other option. Training is an investment and shall be funded as part of the project budget.
5. Boiler manufacturer installer training with specifics and hands on detail were needed – that is being addressed separately.
6. Address the above items and lead by example.

189

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Misc Other Relevant Discussion Topics

190

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

TBD more slides if  
Needed, but there is  
enough above already  
for the detailed Stage-II  
Course

### Take Home Messages & Next Steps (**Questions**)

1. Based on what has been discussed earlier, list 3 to 5 Major “Take Home Messages for your projects Next Steps” ?
2. If you were to select the most substantial item, what would you select and why?



## Take Home Messages & Next Steps

1. In general, biomass heating systems require a more *careful, thorough, integrated and methodical* approach than conventional oil or gas heating systems.
2. Invest in good quality comprehensive ASHRAE Level-II or -III Building Energy Audits *before* making any further major design and/or capital improvement project decisions.
3. Moreover, district biomass heating systems serving multiple buildings and HXs require *additional attention* compared to single building systems.
4. Make next system makeover steps only *after* a careful review of the reported Issues Summary & Observations including lack of **Cx**, TAB, Sequences, updated drawings, updated pump/valve schedules, hydronic details, HX reminders, independent 3<sup>rd</sup> party design review, take/verify as-built Temperature and Flow measurements, and provide proper documentation, etc.

Can  
Update  
Slide Later

193

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Take Home Messages & Next Steps - Cont.

5. In general, the design engineering firm selection (or design-build firm selection) in such projects should illustrate that they have enough central plant, hydronics, controls, Cx & biomass system experience (and a good relationship with competent TAB contractors); Any additional needed skills shall be sought via training and/or sub-consulting with experts.
6. Future design, controls and TAB/Cx work scopes shall consider all the points brought up in this presentation covering *both* the building's secondary systems (distribution and all UVs and AHUs) and the primary systems; i.e., the hybrid oil/biomass boiler project with full TAB, flows and controls integration of all systems (all boilers, all pumps, all pipes, all modulating valves, all balancing valves, all check valves, HXs, all tank [TES and expansion], etc.) to mitigate against any "potential" system pressurization, flow imbalances or control conflicts between the two boiler types and between the primary and secondary systems to attain and operate a successful baseloaded biomass heating plant with supplemental oil heating capacity.

Can  
Update  
Slide Later

194

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

7. Take *baseline measurements* to troubleshoot the operation of the new/existing oil boilers, determine their measured output, and have better baseline resolution for M&V.
8. Take *baseline measurements* and bench mark for major hotwater, steam and direct propane end uses, including but not limited to the mixed fuel kitchen: Propane Cooking, Steam Cooking & Steam for Dishwasher booster (from the steam fired propane boiler), Exhaust fans flow and their electricity usage, etc.
9. Take *baseline measurements* and bench marks for major end uses like the electric kitchen or summer DHW boiler before making any further capital decisions like CHP, which may not be an appropriate measure for the building.
10. Generally, taking selected *baseline measurements* and bench marks for major end uses as exemplified above is part of good energy management and control enhancements. Invest in as-built building HVAC system TAB before adding any biomass heating systems.

Can  
Update  
Slide  
Later

195

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

11. Consider the list of *EEMs* included earlier in this presentation as part of future capital project thoughts and/or Master Energy Plans and obviously add more as you find appropriate. Approach meaningful and well thought through improvements as opposed to rushed ones to avoid any further system issues (like the existing oil boilers suspected suppressed capacity with no TAB work); start with making plans to correct the existing oil boiler plant issues during planning for the biomass projects, do both in an integrated approach preferably using the same competent design firm and suggest they seek knowledge in needed areas and attend necessary trainings as discussed earlier.
12. *Under-sizing* biomass boilers attains longer on cycles/runtimes at higher/full loads & less off cycles, especially when coupled with Thermal Energy Storage (TES) tanks. Carefully consider the different biomass boiler sizing calculation options presented earlier in this presentation (or the other presentation). Additionally, an undersized/properly sized *tandem biomass boiler* setup could provide better pellet plant performance during part load conditions.

Can  
Update  
Slide  
Later

196

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

13. Completely revise the TES Buffer Tank design: Use *2-pipe tank* vs. 4-pipe tank, use a much taller tank with more storage capacity, use either horizontal perforated diffusers or preferably diffuser trays. This is to reduce potential future pellet boiler cycling, attain faster biomass loop response times, higher efficiencies, and displace more fossil fuel.
14. Unfortunately, however, a taller tank with more storage capacity cannot be accommodated in the limited capacity container (ceiling height limitations). An additional external larger vertical elaborate TES tank was not discussed due to cost and needed piping changes to accommodate a second TES tank.

Can Update  
Slide Later

197

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

15. Moving forward, (1) carefully design all the pipes, pumps, VFDs and valves according to observations in the independently generated system assessment Memos to attain *better balance upstream and downstream of the TES tank to enhance its thermal stratification*. In another case, do the same (2) after relocating the heat exchanger to its new and correct location between the tank and loop as opposed to its current incorrect location between the biomass boiler and the tank. In another case, do the same (3) after relocating P-2 from the return to the supply side of the loop pipes and after upsizing all 3 heat exchangers to address several issues identified from the current setup (to prevent the P-2 pump cavitation, reduce trapped air, and alleviate building bottlenecked HX capacity).
16. Existing fuel oil fired boilers can serve as backup or supplement to undersized biomass heating systems and to meet peak building heating loads that exceed the future baseloaded biomass heating plant output capacity; However, ensure the oil boilers have good turn down capabilities, which is not always the case, causing them to frequently cycle..... Consider upgrading the existing oil boiler controls to prevent them from frequent cycling.

Can Update  
Slide Later

198

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

17. Review stack considerations, especially once the biomass boilers take away heating load from the existing oil boilers, to address any potential condensation issues in the existing brick stack and consider the needed stainless steel inner liner.
18. Must Methodically Design, Commission, TAB, Measure & Verify (M&V), and have independent design reviews to ensure proper biomass system integration with existing heating systems, energy management systems, and heat distribution systems throughout the entire process from design through operation and M&V.

Can Update  
Slide Later

199

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

19. After updating the control sequences, arrange for at least a full day of *formal controls and/or EMS training* and ensure that the plant staff have the necessary knowledge to operate the control system, set up trend logs, and do basic to mid level troubleshooting of controls.
20. **STOP** - Do not rush in any oil boiler or pellet boiler sizing decisions before taking the baseline measurements and performing the TAB recommendations included earlier in this presentation.
21. **STOP** - Do not rush in alternative biomass boiler pump selections (3.0 hp in place of existing 1.5 hp) to do an “apparent” quick fix that does not guarantee addressing all of the issues identified in this memo - We say NO to band aid approach; Use a full, integrated and methodical design approach starting with developing a complete set of drawings along with TAB *before* and *after* any system corrections/enhancements preferably completed by the same contractor to attain project continuity.

Can Update  
Slide Later

200

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps - Cont.

22. Before moving further with a project, carefully review the suggested list of *Roles and Responsibilities* and have a clear path moving forward with clear roles for each member of the project team during all project phases, and with a call for clear collaboration, communication and transparency among the team members proceeding with existing system corrections and future capital projects.
23. Comply with the applicable *RHNY Eligibility Requirements* explained earlier as best practices (and *minimum* requirements) and *exceed* them where needed for the betterment of the project; there is no one size that fits all, Biomass heating project is more complex than an average commercial oil or propane boiler heating projects.
24. Address the above items and lead by example and contact us with any question you may have.

Can Update  
Slide Later

201

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

### Take Home Messages & Next Steps (**Questions**)

1. What have you learned today that can support your other MEP projects, besides just biomass?
2. Out of all of what you have learned today, how much of it is biomass heating system specific vs. generally applicable to any other engineering projects?
3. Before concluding this session, define in your own terms Cx & TAB? You now know why the trainer focused on Cx and TAB as part of system troubleshooting. Definitions will be shared shortly.
4. List major Cx and TAB references you know of or have used in your job.

Can Update  
Slide Later

202

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Project Completion & Closeout Cx Docs (4 Slides)

1. **Cx Plan** (Updated as necessary).
2. **OPR & BOD** (Updated as necessary).
3. **Training Manual** for entire system and all BOP.
4. **System O&M Manual** for entire system & all BOP.
5. **Issues and Resolution Log** (Closeout & completed).
6. Final **Cx Report**.
7. Convene **Lessons Learned Workshop** (Optional, but strongly recommended).
8. **Other TBD** as needed on case by case basis.

Suggested recap on the project Completion & Closeout documents; Start w/ Stage-I 3 slides then this 4<sup>th</sup> slide for Cx Specifics.

Suggested List Courtesy of ASHRAE Cx Resources

203

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

- ASHRAE, founded in 1894, is a global society advancing human well-being through sustainable technology for the built environment. The Society and its more than 50,000 members worldwide focus on building systems, energy efficiency, indoor air quality, refrigeration and sustainability. Through research, standards writing, publishing, certification and continuing education, ASHRAE shapes tomorrow's built environment today. More information can be found at [www.ashrae.org/news](http://www.ashrae.org/news).”
- As some of the above tasks were not yet fully completed in this project (TAB and Cx), we included the above definitions to best support and guide the reader of this Presentation Report during project next steps.

204

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms

205

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms - 1

A/E - Architect and Design Engineers	BOP - Balance of Plant
A1 Bldg - *****	BTU - British Thermal Unit
ACCA - Air Conditioning Contractors of America	Btu/h - British Thermal Unit per Hour
ACT - Air Changes Per Hours (a measure of building infiltration rate)	CA - Commissioning Authority
ADM4 Bldg - *****	CC - Controls Contractor
AEE - Association of Energy Engineers	CCHP - Combined Cooling Heat and Power
AHU - Air Handling Unit	CD - Construction Documents
AMU - Air Makeup Unit	CEA - Comprehensive Energy Audit
ANSI - American National Standards Institute	CEM - Certified Energy Manager
ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers	CGC - Cleaner Greener Communities (A NYSERDA program that includes biomass installations)
ASI - Architect's Supplemental Instructions	CGC - Cleaner Greener Communities (for Biomass Heating System Program Requirements)
ASME - American Society of Mechanical Engineers	CHP - Combined Heat and Power
Avg - Average	CHW - Chilled Water
BAS - Building Automation System (similar to EMS or EMCS)	CIPP - Commercial/Industrial Performance Program
BFP - Boiler Feedwater Pumps	CM - Construction Manager
BLCC - Building Life Cycle Cost Analysis Program by US DOE	CO - Carbon monoxide gas - harmful emissions
BMS - Building Management Systems	CS - Current Transformer
BO - by others	CT - Cooling Tower
BOD - Basis of Design	CT - Current Transformer
	CT Sensors - Current Transducer for measuring Amperage and/or On/Off Motor Status

206

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms - 2

Cx - Commissioning	DOE - United States (US) Department of Energy
Cx Plan - Commissioning Plan Document	DP - Differential Pressure
Cx Report - Commissioning Report	E/A - Engineering/Architectural
Cx Report - Commissioning Report	EA - Energy Audit or Energy Analysis
D2 Bldg - *****	EA Credit - Energy and Atmosphere LEEEC Credit by USGBC
DA - Deaerator Tank in Steam Systems	EB - Existing Building
DAA - Data Acquisition and Analysis	EC - Electrical Contractor
DAS - Data Acquisition System	ECIPP (Enhanced CIPP), and most recently EFP
DBT - Dry Bulb Temperature	ECM - Energy Conservation Measure
DCV - Demand Controlled Ventilation	ECM Motor - Electronically Commutated Motor
DD - Annual Heating Degree Days (typically base 65 °F)	Econo - Economizer
DDC - Direct Digital Control	EEM - Energy Efficiency Measure
DEA - Detailed Energy Analysis	EES - Energy Engineering Services
Deg C - Degrees Centigrade or Celsius	EF - Exhaust Fan
Deg C = (Deg F - 32) x 5/9	Eff - Efficiency
Deg F - Degrees Fahrenheit	EFLH - Equivalent Full Load Hours
Deg F = (1.8 x Deg C) + 32	EFP - Existing Facilities Program
DHW - Domestic hot water	EMCS - Energy Management and Control System
DOAS - Desiccated Outdoor Air Systems	EMS - Energy Management System
Doc - Document	ERU - Energy Recovery Unit

207

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms - 3

ERV - Energy Recovery Ventilator	GTHP - Geothermal Heat Pump
ESCO - Energy Services Company	H&C - Heating and Cooling
ESPC - Energy Savings Performance Contracting	HDD - Annual Heating Degree Days (typically base 65 °F)
EUH - Electric Unit Heater	HELE - High-Efficiency Low-Emissions
EUIs - Energy Utilization Indices	HOO - Home Heating Oil
FCU - Fan Coil Unit	HVAC - Heating, Ventilating and Air-Conditioning Systems
FIMS - Facility Improvement Measures	HW - Hot Water
FlexTech - NYSERDA's Flexible Technical Assistance Program	HWRT - Hot Water Return Temperature
FMS - Facility Management System	HWST - Hot Water Supply Temperature
FPT - Functional Performance Test	HWT - Hot Water Temperature
FT - Functional Performance Test	HX - Heat Exchanger
ft <sup>2</sup> - square feet	IAQ - Indoor Air Quality
FTEs - Full Time Employees	IB - Informational Bulletins
Gal - Gallon	IC - Implementation Contractor - Hired by NYP&A to support some NYS funded Projects
GBE - Green Buildings Engineer	IDP - Integrated Design Process
GC - General Contractor (prime)	IEQ - Indoor Environmental Quality
GD - Guidance Document	Info - Information
GPH - Gallons per Hour (units measuring oil flow into the boiler burner)	IP Units - Imperial or English units of measurements (inch-pound), widely used in the US
GPM - Gallons per Minute (units for measuring fluid flow)	IP Units - Inch-Pound Units
GSA - U.S. General Services Administration.	IPMVP - International Performance Measurement and Verification Protocol

208

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved



## Glossary of Terms, Abbreviations & Acronyms - 4

k - Thousand	MEP - Mechanical, Electrical and Plumbing
kW - The unit boiler capacities are measured by in Europe	MER - Mechanical Equipment Room
LAN - Local Area Network	Mlbs - 1,000 pounds of steam
lb - pound	MM - Million
LEED AP - Leadership in Environmental and Energy Design Accredited Professional by USGBC	MRHL - manual reset high limit switch
Linkage Burner - Boiler burner set to fixed air-to-fuel ratio through mechanical shaft, also referred to as jackshaft control, likely calibrated once or twice a year. Serves many old / existing boilers. Can be set to hi/low fire with no in between modulation. Fixed relationship across firing range results in lower efficiencies than linkageless burners.	MV - Modulating Valve (can be 2-way or 3-way Valve)
Linkageless Burner - Boiler burner programmed to use a linkageless modulating burners that varies air-to-fuel ratio cross the firing range and is equipped with VFD forced draft fans and O2 trim package. Represents an available control option in many modern boilers. Varying relationship across the firing range results in better efficiencies than linkage burners.	N/A - not applicable
LP - Liquefied Propane	NC - New Construction
LWCO - low water cut off switch	NCP - New Construction Program
M - Motorized (applies to an electrically actuated modulating valve)	NESCAUM - Northeast States for Coordinated Air Use Management.
M - Thousand	<b>New Additions in Sept 2019 when I was Finalizing the Cx Documents</b>
M&V - Measurement and Verification (can be for a plan, report or process)	New Items for the Cx Presentation
m <sup>3</sup> /h - Meter <sup>3</sup> per Hour (units for measuring fluid flow)	NG - Natural Gas
m <sup>3</sup> /hr (1) = 1,000 L/m <sup>3</sup> / (3.78541 Liters/Gallon x 60 minutes / hr) = 4.402869614 GPM	NY - New York
MBCx - Monitoring-Based Commissioning	NYPA - New York Power Authority
MBH - Boiler rated output capability (1,000 Btu/h)	NYS - New York State
MC - Mechanical (HVAC and Plumbing) Contractor	NYS DEC - New York State Department of Environmental Conservation
	NYSERDA - New York State Energy Research and Development Authority
	O&M - Operating and Maintenance
	OA - Outside or Outdoor Air
	OAT - Outside Air Temperature
	OH&P - Overhead and Profit
	OPR - Owner's Project Requirements

209

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms - 5

OS - Operating System	PP - Per Person
OSHA - Occupational Safety & Health Administration	PPM - Parts per million (A unit to measure Carbon monoxide (CO) Emissions)
P - Pump	PQ - Power Quality
PA - Project Application	PRVs - Pressure Reducing Valves or Pressure Regulating Valves
PB - Pellet Boiler	PSD - Proposed System Design
PC - Prefunctional Checklist	psia - pounds per square inch absolute pressure (applies to hot water, steam or refrigerant systems)
PDH - Professional Development Hours	psig - pounds per square inch gauge pressure (applies to hot water, steam or refrigerant systems)
PE - Professional Engineer	PT Ports - Pressure and Temperature Ports needed for TAB work
PECI - Portland Energy Conservation, Inc. - Developed The Model Commissioning Plan - Construction Phase Version 2.05 under the initial sponsorship of the U.S. Department of Energy and later sponsorships by the Oregon Office of Energy and PECE. As PECE later switched its focus, the Cx, PFC and FPT material was transferred, managed and updated by BCA - BCxA (Building Commissioning Association).	PTAC - Packaged Terminal Air-Conditioning Unit
PFC - Prefunctional Checklist	PTE - Part-Time Employee
PFHX - Plate and Frame Heat Exchanger	PV - Photovoltaic
PG - Propylene glycol mix - antifreeze	PWD - Password
PID - Piping and Instrumentation Diagram	Q - Energy (can be input, output, loss, stored, created, space or building heat load, etc.)
PIR - Post Installation Report	QC - Quality Control
PLC - Programmable Logic Controller	R&D - Research and Development
PM - Project Manager	R&R - Range and Relational Checks (to verifications the quality of collected data)
PM 2.5 - Fine particulate matter emission - an air pollutant - refers to tiny particles or droplets in the air that are 2.5 microns or less in width.	R&R - Roles & Responsibilities
POC - Point of Contact	RA - Return Air
PON - Program Opportunity Notice (a solicitation issued by NYSERDA)	RAT - Return Air Temperature
	RDD - Research and Development and Demonstration
	RE - Renewable Energy Systems

210

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

## Glossary of Terms, Abbreviations & Acronyms - 6

<p>REDC - Regional Economic Development Councils</p> <p>REDGHG - The Regional Economic Development and Greenhouse Gas Reduction Program (PON 2571)</p> <p>RFI - Requests for Information</p> <p>RFP - Request for Proposal</p> <p>RH - Relative Humidity</p> <p>RH&amp;C - Renewable heating and Cooling.</p> <p>ROI - Return on Investment</p> <p>RTDs - Resistance Temperature Detectors (basically temperature sensors)</p> <p>RTU - Rooftop Unit</p> <p>S3 Bldg - *****</p> <p>SAAF - Site Assessment Application Form</p> <p>SAR - Site Assessment Report</p> <p>SAT - Supply Air Temperature</p> <p>SC - Sheet Metal Contractor</p> <p>SCADA - System Control and Data Acquisition</p> <p>SF - Supply Fan</p> <p>SI Units - International or Metric System Units of Measurements</p> <p>SME - Subject Matter Expert</p> <p>SOO - Sequence of Operations</p> <p>SOPs - Standard Operating Procedures</p>	<p>SOPs - Written Standard Operating Procedures</p> <p>SOS - State of the State Address by Governor Cuomo</p> <p>SPC - Standard Performance Contracting</p> <p>Spec - Specifications</p> <p>SPT - Setpoint (can be for temperature or pressure)</p> <p>Sqft - Square Feet</p> <p>SS - Supply Setpoint Temperature</p> <p>SSPC - Standing Standard Project Committee by ASHRAE</p> <p>STL - Lower (bottom) Tank Setpoint Temperature (Boiler OFF T Setting)</p> <p>STU - Upper (top) Tank Setpoint Temperature (Boiler ON T Setting)</p> <p>Subs - Subcontractors to General</p> <p>TAB - Testing, Adjusting, and Balancing</p> <p>TAS - Technical Assistance Study</p> <p>TC - Technical Consultant</p> <p>TES - Thermal Energy Storage Tank (can also be a slab)</p> <p>TFS - Technical Feasibility Study</p> <p>Tr - Return Temperature (or Entering Temperature)</p> <p>Ts - Supply Temperature (or Leaving Temperature)</p> <p>UH - Unit Heater</p> <p>UPS - Uninterrupted Power Supply (a battery backup)</p>
---	--

## Glossary of Terms, Abbreviations & Acronyms - 7

<p>USGBC - United States Green Buildings Council</p> <p>UV - Unit Ventilator</p> <p>VAV - Variable Air Volume</p> <p>VFD - Variable Frequency Drive</p> <p>VRF - Variable Refrigerant Flow</p> <p>VRV - Variable Refrigerant Volume</p> <p>VSD - Variable Speed Drive</p> <p>WBT - Wet Bulb Temperature</p> <p>WC - Water Closet</p> <p>WC5 Bldg - *****</p>	
--	--

## Glossary of Terms, Abbreviations & Acronyms - 8

**Not Sorted Alphabetically; It groups selected the Commissioning related Organization and Certifications together:**

TBCxP - Total Building Cx Process as defined in ASHRAE Guideline 0 & NIBS

**[1]**

**ASHRAE - American Society of Heating, Refrigerating and Air-Conditioning Engineers**

BCxP - Building Commissioning Professional Certification (Certification issued by ASHRAE)

CPMP - Commissioning Process Management Professional (Certification issued by ASHRAE)

**[2]**

**AABC - Associated Air Balance Council**

**ACG - AABC Commissioning Group**

CxA - Certified Commissioning Authority (Certification issues by ACG)

CxTs - Certified Commissioning Technicians (Certification issues by AABC or ACG)

EMP - Energy Management Professional (Certification issues by ACG)

**[3]**

**AEE - Association of Energy Engineers**

CBCP - Certified Building Commissioning Professional (Certification issued by AEE)

**[4]**

**BCxA - Building Commissioning Association**

**BCA - Building Commissioning Association**

**BCCB - Building Commissioning Certification Board**

CCP - Certified Commissioning Professional (Certification issued by BCCB and BCxA)

ACP - Associate Commissioning Professional (Certification issued by BCCB and BCxA)

BEMP - Building Energy Modeling Professional Certification (Certification issues by ASHRAE & is a prerequisite for the CCP certification)

**[5]**

**University of Wisconsin-Madison**

**Descriptions of Certifications for Educational Achievement:**

QCxP - Accredited Qualified Commissioning Process Provider

BECxP - Accredited Building Enclosure Commissioning Process Provider

CxA+BE - Accredited Commissioning Authority + Building Enclosure

**Descriptions of Certifications for Educational Achievement Plus Project Experience:**

CxAP - Commissioning Process Authority Professional

CxM - Commissioning Process Manager

CxTS - Commissioning Process Technical Service Provider

GCxP - Green Commissioning Process Provider

## Glossary of Terms, Abbreviations & Acronyms - 9

**[6]**

**NEBB - National Environmental Balance Bureau**

BSC CP - Building System Commissioning Certified Professional

BSC CxCT - Building System Commissioning Certified Technician

CxPP - Commissioning Process Professional Certified Professional

RCx-EB CP - Retro-Commissioning of Existing Buildings Certified Professional

**[7]**

**NIBS - National Institute of Building Sciences (Defines the Total Building Cx Process).**

NCBC - National Conference on Building Commissioning.

**[8]**

**SMACNA - Sheet Metal & Air Conditioning Contractors' National Association**

**[9] Misc Other Abbreviations**

BPA - Bonneville Power Administration.


BPI - Building Performance Institute.

BPA - Building Performance Association.



## Q/A

*Thank you all for Attendance and Participation*

Khaled A. Yousef, PE, CEM, CDSM, LEED AP, GBE  
 Principal Energy Engineer / Founder  
 Pyramid Energy Engineering Services, PLLC (Pyramid EES)   
 30 Karner Road #12369, Albany, NY 12212, USA  
[Khaled.A.Yousef@PyramidEES.com](mailto:Khaled.A.Yousef@PyramidEES.com)  
 +1 (518) 221-7382  
[www.PyramidEES.com](http://www.PyramidEES.com)

Energy Efficiency & Sustainability | Optimization | Modeling | Technical & Design Assistance  
 | Master Planning | LEED Support | Commissioning | CHP | Biomass | RH&C | R&D

*Thank you*  *NYSERDA* *for your support*

215

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved

**End**



216

Proper Cx for Commercial Installations From Intro to Detail in NYS 20191025 (V1a)

© (2019) Pyramid EES. Rights reserved